

General Disclaimer

One or more of the Following Statements may affect this Document

- This document has been reproduced from the best copy furnished by the organizational source. It is being released in the interest of making available as much information as possible.
- This document may contain data, which exceeds the sheet parameters. It was furnished in this condition by the organizational source and is the best copy available.
- This document may contain tone-on-tone or color graphs, charts and/or pictures, which have been reproduced in black and white.
- This document is paginated as submitted by the original source.
- Portions of this document are not fully legible due to the historical nature of some of the material. However, it is the best reproduction available from the original submission.

DOE/NASA CONTRACTOR REPORT

DOE/NASA CR-150614

SYSTEM DESIGN PACKAGE FOR IBM SYSTEM ONE SOLAR HEATING AND DOMESTIC HOT WATER

Prepared by

IBM Corporation
Federal Systems Division
150 Sparkman Drive
Huntsville, Alabama 35805

Under Contract NAS8-32036 with

National Aeronautics and Space Administration
George C. Marshall Space Flight Center, Alabama 35812

For the U. S. Department of Energy



(NASA-CR-150614) SYSTEM DESIGN PACKAGE FOR
IBM SYSTEM ONE: SOLAR HEATING AND DOMESTIC
HOT WATER (IBM Federal Systems Div.) 174 p
HC A08/MF A01 CSCL 10A

N78-21589

Unclass

G3/44 14124

U.S. Department of Energy



Solar Energy

1. REPORT NO. DOE/NASA CR-150614	2. GOVERNMENT ACCESSION NO.	3. RECIPIENT'S CATALOG NO.	
4. TITLE AND SUBTITLE System Design Package for IBM System One Solar Heating and Domestic Hot Water		5. REPORT DATE February 1977	
		6. PERFORMING ORGANIZATION CODE	
7. AUTHOR(S)		8. PERFORMING ORGANIZATION REPORT #	
9. PERFORMING ORGANIZATION NAME AND ADDRESS IBM Corp, Federal Systems Division 150 Sparkman Drive Huntsville, Alabama 35805		10. WORK UNIT NO.	
		11. CONTRACT OR GRANT NO. NAS8032036	
12. SPONSORING AGENCY NAME AND ADDRESS National Aeronautics and Space Administration Washington, D. C. 20546		13. TYPE OF REPORT & PERIOD COVERED Contractor Report	
		14. SPONSORING AGENCY CODE	
15. SUPPLEMENTARY NOTES This work was done under the technical management of Mr. Earle G. Harris, George C. Marshall Space Flight Center, Alabama.			
16. ABSTRACT This report is a collation of documents and drawings that describe a prototype solar heating and hot water system using air as the collector fluid and a pebble bed for heat storage. The system was designed for installation into a single-family dwelling. The description, performance specification, subsystem drawings, verification plan/procedure, and hazard analysis of the system are packaged for evaluation of the system with information sufficient to assemble a similar system. The first system (1A) solar heating and domestic hot water is in operation at the Home Builders Association, 2809 Burks Road, SW, Huntsville, Alabama. The second system (1B) is being installed at the U. S. Department of Interior, National Park Service, Carlsbad Caverns, New Mexico, Residence "L."			
17. KEY WORDS		18. DISTRIBUTION STATEMENT Unclassified-Unlimited  WILLIAM A. BROOKSBANK, JR. Manager, Solar Heating and Cooling Project Ofc	
19. SECURITY CLASSIF. (of this report) Unclassified	20. SECURITY CLASSIF. (of this page) Unclassified	21. NO. OF PAGES 175	22. PRICE NTIS


INDEX

	<u>Page</u>
System Description	1
System 1 Design Heating and Hot Water - 7933608	5
Performance Specification - 7933444	B-i
Collector Subsystem - 7933609	C-1
Energy Storage Subsystem - 7933610	D-1
Energy Transport Subsystem - 7933611	D-8
Solar Air Handler - 7933623	D-10
Partial Back Draft Damper - 7933625	D-11
Hot Water Subsystem - 7933612	D-12
Control Subsystem - 7933613	D-14
Interface Control Box - 7933619	D-16
Interface Control Box - 7933620	D-18
Interface Control Box Bracket - 7933621	D-19
Interface Control Box Schematic - 7933622	D-20
Solar Air Controller - 7933624	D-21
Auxiliary Energy Subsystem - 7933614	E-1
Integration Subsystem Specification - 7933615	F-1
Data Collection Subsystem - 7933616	G-1
Instrumentation Program System 1A - IP 7933616	G-3
Verification Plan/Procedure - 7933445	H-1
Verification Summary System 1A - November 19, 1976	I-1
Hazard Analysis	J-1

SYSTEM DESCRIPTION

Prototype System I has been designed by IBM under contract NAS8-32036 to NASA Marshall Space Flight Center as a solar heating and hot water preheat system for a single family dwelling. The system uses air collectors and a pebble bed storage. Domestic water is preheated with a heat exchanger in the hot air duct. Domestic water is preheated with a heat exchanger in the hot air duct.

Figure 1-1 is a pictorial illustration of the system, which was designed for installation on a dwelling in the 1500 to 2500 square foot range. The design can be scaled up or down to accommodate a wide range of heating and hot water requirements for other single family, multi-family or commercial buildings without significant change to the design concept.



ORIGINAL PAGE IS
OF POOR QUALITY

Figure 1-1. Typical Solar Heating and Hot Water System using Air type collectors.





Figure 1-2. Principal Elements of system.

Principal elements of the system are (1) flat plate air type solar collectors, (2) a pebble bed for thermal storage of collected solar energy, (3) an air handling unit to move and direct the air through the energy transport system, (4) an air-to-water heat exchanger and circulating pump to allow for transfer of heat from the collector/storage circuit to the domestic hot water circuit, (5) a domestic hot water pre-heat tank for storage and transfer of collected energy into the conventional domestic water heater, (6) an air-to-air heat pump and electric strip heaters to supply auxiliary energy during periods of insufficient solar insolation, and (7) a ducting system to convey the solar heated air between system components and into the heated space. These elements are shown in Figure 1-2 (above).


IBM SYSTEM 1A

Office Building for the

Home Builders Association of Huntsville, AL



RELEASED FOR ASM	QTY	TECHNICAL APPROVAL		SYM	DATE	CHANGE NO	SYM	DATE	CHANGE NO	7933608
		ELEC								DEVELOPMENT NO
		METAL								
		PLASTIC								



ORIGINAL PAGE IS
OF POOR QUALITY


SHEET 1 OF 2

IBM MATERIAL NO			MUST CONFORM TO ENG SPEC 890350			IBM	
IBM MATL ALTERNATE NO			TOLERANCES UNLESS OTHERWISE NOTED			NAME SYSTEM ONE	
		SCALE NONE	INCH			DESCRIPTION	
CASE DEPTH			LINEAR ±			DESIGNER	L CLARK 10/11
HARDNESS			ANGLES ±			DETAILER	J PERRY 11/11
		THIRD ANGLE PROJECTION	RADI UNLESS OTHERWISE NOTED			DWG CHK	
S. RFACE TREATMENT		INCH mm	EDGE CORNER BREAKS	OUTSIDE MAX	DSGN APPRO	J. Robinson 11/11	
				INSIDE MAX	CLASSIFICATION		

8093367

C

RELEASED FOR ASM	QTY	TECHNICAL APPROVAL			SYM	DATE	CHANGE NO	SYM	DATE	CHANGE NO	7933608
		ELEC									DEVELOPMENT NO
		METAL									
		PLASTIC									



SYSTEM 1 IS A SOLAR HEATING & HOT WATER SYSTEM USING AIR COLLECTORS & ROCK STORAGE WITH AN AIR-TO-WATER HEAT EXCHANGER FOR WATER HEATING.

THE SYSTEM IS COMPRISED OF SEVEN OPERATIONAL SUBSYSTEMS:

COLLECTOR SUBSYSTEM	P/N 7933609
ENERGY STORAGE SUBSYSTEM	P/N 7933610
ENERGY TRANSPORT SUBSYSTEM	P/N 7933611
HOT WATER SUBSYSTEM	P/N 7933612
CONTROL SUBSYSTEM	P/N 7933613
AUXILIARY ENERGY SUBSYSTEM	P/N 7933614
INTEGRATION SUBSYSTEM	P/N 7933615
DATA COLLECTION SUBSYSTEM	P/N 7933616
(NOT SHOWN)	

SYSTEM PERFORMANCE IS DELINEATED IN THE PERFORMANCE SPECIFICATION, P/N 7933444, WHICH INCLUDES THE INSTALLATION DRAWINGS, P/N 7933617.

SHEET 2 OF 2
7933608

IBM MATERIAL NO			MUST CONFORM TO ENG SPEC R90350						
IBM MATL ALTERNATE NO									
CASE DEPTH		SCALE	NONE	TOLERANCES UNLESS OTHERWISE NOTED	INCH	mm	NAME	SYSTEM ONE DESCRIPTION	
HARDNESS				LINEAR ±			DESIGNER		
SURFACE TREATMENT				ANGLES ±			DETAILER		
				RADI UNLESS OTHERWISE NOTED			DWG CHK		
80933608	B			EDGE/CORNER BREAKS	OUTSIDE MAX		DSGN APPRO		
					INSIDE MAX		CLASSIFICATION		

ARTS IST	IBM	FEDERAL SYSTEMS DIVISION CODE IDENT 20234 - HUNTSVILLE, AL CODE IDENT 52088 - MANASSAS VA CODE IDENT 03640 - OWEGO, NY	CONTRACT NO	CODE * IDENT	REVIS
				20234 PL 7933608	LTR + DATE 08

TITLE	EN NO.	SHEET
SYSTEM 1 DESIGN HEATING & WATER		01

1	REFERENCE DESIGNATION	QUANTITY REQUIRED	UNIT MEAS	CODE IDENT	DRAWING OR DOCUMENT NO	PART OR IDENTIFYING NO.	NOMENCLATURE OR DESCRIPTION
	EMS COMMON TO PART NUMBER	7933608					
		1	01			7933609	COLLECTOR SUBSYSTEM
		1	01			7933610	ENERGY STORAGE SUBSYSTEM
		1	01			7933611	ENERGY TRANSPORT SUBSYSTEM
		1	01			7933612	HOT WATER SUBSYSTEM
		1	01			7933613	CONTROL SUBSYSTEM
		1	01			7933614	AUX ENERGY SUBSYSTEM
		1	01			7933615	INTEGRATION SUBSYSTEM
		1	01			7933616	SDC SUBSYSTEM-IBM SYSTEM 1

UNIT OF MEASURE CODE 01 - PIECE EACH 11 - INCH 12 - FEET 18 - CUBIC FOOT 31 - OUNCE (AVDP) 35 - OUNCE (TROY)	59 - FLUID OUNCE 66 - CUBIC INCH	SYMBOL CODE (SY): V - VENDOR ITEM. SEE SPECIFICATION OR SOURCE CONTROL DRAWING PLANNING CODE (PL): K - ALTERNATE ITEM P - BULK MATL (ALL OTHER PL CODES ARE FOR IBM REF ONLY: EG. G - GOVT FURN ITEM J - AS REQD L - DO NOT FILL N - VENDOR FURN R - REF X - DO NOT GENERATE Z - DUMMY CONNECT) CHARACTER CODE (CH): A - WITH BILL OF MATL D - WITHOUT BILL OF MATL R - FACTORY REF
--	-------------------------------------	---

DWG NO.

CHK ENGRG NOTICED LTR

DESCRIPTION

DATE

APPROVED

CONTR NO. NASS-32036		INTERNATIONAL BUSINESS MACHINES CORP. FEDERAL SYSTEMS DIVISION HUNTSVILLE, ALA. 35807	
PREPARATION <i>Gl. Sigler 11/2/76</i>		TITLE SYSTEM PERFORMANCE SPECIFICATION FOR SIMS PROTOTYPE SYSTEM DESIGN NO. 1	
DSGN CHK			
DWG CHK			
DSGN APPROVAL <i>VH. Johnson 11/2/76</i>		SIZE A	CODE IDENT NO.
			DWG NO. 7933444
		SCALE	WT
			SHEET

55-1685-0

A B-i

TABLE OF CONTENTS

- 1.0 INTRODUCTION
- 2.0 APPLICABLE DOCUMENTS
- 3.0 APPLICABILITY OF IPC
- 4.0 DEVIATIONS FROM IPC
- 5.0 GOVERNMENT FURNISHED PROPERTY
- 6.0 GOVERNMENT DIRECTED REQUIREMENTS
- 7.0 GEOGRAPHICAL AREA
- 8.0 SYSTEM APPENDICES

APPENDIX A

- A-0 SYSTEM IDENTIFICATION
- A-1 SYSTEM PERFORMANCE
- A-2 INSTALLATION DRAWINGS

ORIGINAL PAGE IS
OF POOR QUALITY

1.0 INTRODUCTION

This performance specification establishes the requirements for the design and performance of the solar heating and domestic hot water system utilizing air collectors and a heat pump auxiliary energy subsystem. It designates the Interim Performance Criteria applicable to this type system and defines the deviations. The appendices specify the system performance for each defined site location and system size, the installation drawings, and the detailed configuration diagrams and drawings.

2.0 APPLICABLE DOCUMENTS

The following documents form a part of this specification to the extent specified herein. Specific document reference made in subsequent shall be by basic title or reference number only.

2.1 Government Documents

Interim Performance Criteria for Solar Heating and Combined Heating/Cooling Systems and Dwellings, January 1, 1976, U. S. Department of Housing and Urban Development.

Intermediate Minimum Property Standards for Solar Heating and Domestic Hot Water Systems, April 1976, NBSIR 76-1059, U. S. Department of Housing and Urban Development.

SIMS Contract Statement of Work, NAS8-32036, April 4, 1976 (with current modifications).

2.2 IBM Documents

The following document is referenced for information only:

System One, Description of; 12 November 1976, 7933608.

3.0 APPLICATION OF INTERIM PERFORMANCE CRITERIA BY TYPE OF SYSTEM

The application of each paragraph of the Interim Performance Criteria (IPC) to this type of system is provided in Table I. Since this system provides solar heating and hot water, system type "H" designates the IPC application to this system.

4.0 DEVIATION FROM INTERIM PERFORMANCE CRITERIA

The IPC deviations identified by subsystem evaluation are listed in the following paragraph.

4.1 Deviations to Residential IPC

The collector subsystem evaluation has identified three areas of non-conformance. These IPC requirements are: (1) ultimate load combination (paragraph 3.2.1), (2) resistance to damage (paragraph 3.3.1), and (3) transmission losses due to outgassing (paragraph 5.2.6). No vendor data was available to substantiate these requirements can be met.

4.2 Deviation of Commercial IPC

Not applicable.

5.0 GOVERNMENT FURNISHED PROPERTY

The following items shall be provided by the government:

- (1) Collector subsystem: Solar Energy Products Air Collectors (Model No. EF-212).
- (2) Differential Thermostat: Rho Sigma (Model No. 106).

ORIGINAL PAGE IS
OF POOR QUALITY

TABLE I

RESIDENTIAL SYSTEMS, INTERIM PERFORMANCE CRITERIA SUMMARY			
Sheet <u>1</u> of <u>7</u>			
<u>APPLICATION</u>		<u>TYPE SYSTEMS</u>	
A - APPLICABLE TO SYSTEMS INDICATED		H - HEATING	
I - APPLICABLE TO SYSTEM AND BUILDING		HC - HEATING AND COOLING	
NA - NOT APPLICABLE		HW - HOT WATER ONLY	
RESIDENTIAL INTERIM PERFORMANCE CRITERIA PARAGRAPH	TYPE SYSTEM H	RESIDENTIAL INTERIM PERFORMANCE CRITERIA PARAGRAPH	TYPE SYSTEM. H
1.1 H and HC System Performance	A	1.3.1 Collector Efficiency	A
1.1.1 Heating Design Temperatures	I	1.4 Thermal Storage	A
1.1.2 Cooling Design Temperatures	NA	1.4.1 Storage Capacity and Rate	A
1.1.3 Relative Humid- ity and Water Vapor Pressure	I	1.5 Habitability of Occupied Spaces	A
1.1.4 Solar Contribution	A	1.5.1 Heat or Humidity Transfer Effects	I
1.1.5 Operation Impairment	A	1.6 Energy Transport Efficiency	A
1.2 HW System Subsystem Performance	A	1.6.1 Thermal Losses and Electrical Power	A
1.2.1 Water Design Temperature	I	1.7 Control	A
1.2.2 Storage Design Capacity	A	1.7.1 Installation and Maintenance	A
1.2.3 Solar Contribution	A	1.7.2 Manual Adjustment	A
1.2.4 Operational Impairment	A	1.7.3 Inhabited Space Temperature	A
1.3 Collector Performance	A	1.7.4 Hot Water Tempera- ture	A
		1.8 Auxiliary Energy	A
		1.8.1 Design Loads	A

TABLE I (CONTINUED)

RESIDENTIAL SYSTEMS, INTERIM PERFORMANCE CRITERIA SUMMARY

Sheet 2 of 7APPLICATION

A - APPLICABLE TO SYSTEMS INDICATED
 I - APPLICABLE TO SYSTEM AND BUILDING
 NA - NOT APPLICABLE

TYPE SYSTEMS

H - HEATING
 HC - HEATING AND COOLING
 HW - HOT WATER ONLY

RESIDENTIAL INTERIM PERFORMANCE CRITERIA PARAGRAPH	TYPE SYSTEM	RESIDENTIAL INTERIM PERFORMANCE CRITERIA PARAGRAPH	TYPE SYSTEM
	H		H
2.1 System Design Conditions	A	2.3 Leakage Prevention	A
2.1.1 Equipment Capabilities	A	2.3.1 Pressure Test Nonpotable Fluids	A
2.1.2 Noise or Erosion-Corrosion	A	2.3.2 Pressure Test: Potable Water	A
2.1.3 Operating Conditions	A	2.3.3 Air Transport Systems	A
2.1.4 Fluid Flow in Collectors	A	2.4 Collector Adjustment	A
2.1.5 Entrapped Air	A	2.4.1 Orientation and Tilt	A
2.1.6 Thermal Expansion of Fluids	A	2.4.2 Mutual Shadowing	A
2.1.7 Pressure Drops	A	2.5 Subsystem Isolation	A
2.1.8 Condensate Removal	NA	2.5.1 Shutdown in Multi-family Housing	A
2.2 Mechanical Stresses	A	2.6 Heat Transfer Fluid Quality	A
2.2.1 Vibration Stress Levels	A	2.6.1 Liquid Quality	A
2.2.2 Vibration from Moving Parts	A	2.6.2 Air Quality	A
2.2.3 Water Hammer	A	2.6.3 Fluid Quality	A
2.2.4 Vacuum Relief Protection	A	2.6.4 Freezing Protection	A
2.2.5 Thermal Changes	A	2.7 Piping Supports	A
2.2.6 Flexible Joints	A	2.7.1 Applicable Plumbing Standards	A

TABLE I (CONTINUED)

RESIDENTIAL SYSTEMS, INTERIM PERFORMANCE CRITERIA SUMMARY			
Sheet 3 of 7			
APPLICATION		TYPE SYSTEMS	
A - APPLICABLE TO SYSTEMS INDICATED		H - HEATING	
I - APPLICABLE TO SYSTEM AND BUILDING		HC - HEATING AND COOLING	
NA - NOT APPLICABLE		HW - HOT WATER ONLY	
RESIDENTIAL INTERIM PERFORMANCE CRITERIA PARAGRAPH	TYPE SYSTEM H	RESIDENTIAL INTERIM PERFORMANCE CRITERIA PARAGRAPH	TYPE SYSTEM H
2.8 Excessive Pressure and Temperature Protection	A	3.5.1 Design Provisions	I
2.8.1 Relief Valves and Vents	A	3.6 Creep and Residual Deflection	I
3.1 Structural Design Basis	A	3.6.1 Deflection Limita- tions	I
3.1.1 Applicable Standards	A	3.7 Hail Resistance	A
3.1.2 Service Loads	A	3.7.1 Hail Size and Loading	A
3.2 Failure Loads and Load Capacity	A	3.8 Constraint Loads	A
3.2.1 Ultimate Load Combinations	A	3.8.1 Foundation Settle- ment	A
3.2.2 Ice Loads	A	3.8.2 Constrain Loads	A
3.2.3 Vehicular Loads	I	3.9 Ponding Condition	A
3.2.4 Load Capacity	A	3.9.1 Design Provisions	A
3.3 Damage Control	A	4.1 Plumbing and Electrical Installation	A
3.3.1 Resistance to Damage	A	4.1.1 Plumbing Codes	A
3.3.2 Glazing Design	A	4.1.2 Electrical Codes	A
3.4 Cyclic Loads	A	4.2 Fail-Safe Controls	A
3.4.1 Deflection Limitations	A	4.2.1 System Failure Prevention	A
3.5 Cutting of Structural Elements	I	4.2.2 Automatic Pressure Relief Valves	A

TABLE I (CONTINUED)

RESIDENTIAL SYSTEMS, INTERIM PERFORMANCE CRITERIA SUMMARY			
Sheet <u>4</u> of <u>7</u>			
<u>APPLICATION</u>		<u>TYPE SYSTEMS</u>	
A - APPLICABLE TO SYSTEMS INDICATED		H - HEATING	
I - APPLICABLE TO SYSTEM AND BUILDING		HC - HEATING AND COOLING	
NA - NOT APPLICABLE		HW - HOT WATER ONLY	
RESIDENTIAL INTERIM PERFORMANCE CRITERIA PARAGRAPH	TYPE SYSTEM	RESIDENTIAL INTERIM PERFORMANCE CRITERIA PARAGRAPH	TYPE SYSTEM
	H		H
4.3 Fire Safety	A	4.7 Excessive Surface Temperatures	A
4.3.1 Applicable Fire Standards	A	4.7.1 Protection from Heated Components	A
4.3.2 Penetrations through Fire Rated Assemblies	I	5.1 Effects of External Environment	A
4.4 Toxic	A	5.1.1 Solar Degradation	A
4.4.1 Provisions of Catch Basins	A	5.1.2 Soil Corrosion	A
4.4.2 Detection of Toxic and Flammable Fluids	A	5.1.3 Airborne Pollutants	A
4.5 Safety	I	5.1.4 Dirt Retention on Cover Plate Surface	A
4.5.1 Emergency Egress and Access	I	5.1.5 Abrasive Wear	A
4.5.2 Identification and Location of Controls	A	5.1.6 Fluttering by Wind	A
4.6 Protection and Potable Water and Circulated Air	A	5.2 Temperature and Pressure Resistance	A
4.6.1 Contamination by Materials	A	5.2.1 Thermal Degradation	A
4.6.2 Separation of Circulation Loops	A	5.2.2 Deterioration of Heat Transfer Fluids	A
4.6.3 Backflow Prevention	A	5.2.3 Thermal Cycling Stresses	A
4.6.4 Growth of Fungi	A	5.2.4 Leakage	A
		5.2.5 Deterioration of Gaskets and Sealants	A

RESIDENTIAL SYSTEMS, INTERIM PERFORMANCE CRITERIA SUMMARY

Sheet 5 of 7

<u>APPLICATION</u>		<u>TYPE SYSTEMS</u>	
A - APPLICABLE TO SYSTEMS INDICATED		H - HEATING	
I - APPLICABLE TO SYSTEM AND BUILDING		HC - HEATING AND COOLING	
NA - NOT APPLICABLE		HW - HOT WATER ONLY	
RESIDENTIAL INTERIM PERFORMANCE CRITERIA PARAGRAPH	TYPE SYSTEM H	RESIDENTIAL INTERIM PERFORMANCE CRITERIA PARAGRAPH	TYPE SYSTEM H
5.2.6 Transmission Losses Due to Outgassing	A	6.1.5 Filters	A
5.3 Chemical and Compati- bility of Components	A	6.1.6 Potable Water Shutoff	A
5.3.1 Materials/Transfer Fluid Compatibility	A	6.2 Installation, Operation and Mainte- nance Manual	A
5.3.2 Corrosion of Dissimilar Materials.	A	6.2.1 Installation Instructions	A
5.3.3 Corrosion by Leachable Substnace	A	6.2.2 Maintenance and Operation Instructions	A
5.3.4 Effects of Decom- position Products	A	6.2.3 Maintenance Plan	A
5.4 Components Involving Moving Parts	A	6.2.4 Replacement Parts	A
5.4.1 Wear and Fatigue	A	6.3 Repair and Service Personnel	A
6.1 Accessibility for Maintenance	A	6.3.1 Maintenance of H and HC Systems	A
6.1.1 Access for System Maintenance	A	6.3.2 Maintenance of DHW System	A
6.1.2 Access for System Monitoring	A	7.1 Design	I
6.1.3 Draining and Filling of Liquids	A	7.1.1 Dwelling Design	I
6.1.4 Flushing of Liquids Subsystems	A	7.1.2 Mobile Home Design	I
		7.1.3 Site Design	I
		7.1.4 Passive Use of Solar Energy	I

TABLE I (CONTINUED)

RESIDENTIAL SYSTEMS, INTERIM PERFORMANCE CRITERIA SUMMARY			
		Sheet <u>6</u> of <u>7</u>	
APPLICATION		TYPE SYSTEMS	
A - APPLICABLE TO SYSTEMS INDICATED		H - HEATING	
I - APPLICABLE TO SYSTEM AND BUILDING		HC - HEATING AND COOLING	
NA - NOT APPLICABLE		HW - HOT WATER ONLY	
RESIDENTIAL INTERIM PERFORMANCE CRITERIA PARAGRAPH	TYPE SYSTEM	RESIDENTIAL INTERIM PERFORMANCE CRITERIA PARAGRAPH	TYPE SYSTEM
	H		H
7.2 Adequate Space	I	8.3 Mechanical and Electrical Functioning of Connections	I
7.2.1 Collector Area	I		
7.2.2 Storage Area	I	8.3.1 Plumbing Connections	I
7.2.3 Utility Chases	I		
7.3 Functioning of Dwelling Site	I	8.3.2 Electrical Connections	I
7.3.1 Space Use	I		
7.3.2 Shading of Adjacent Structures	I	9.1 Structures Integrity	I
7.3.3 Impact on Environment	I		
7.3.4 View	I	9.1.1 Movement in Adjacent Structures	I
8.1 Interference with Mechanical Operation	I		
8.1.1 Blockage of Solar Subsystem	I	9.2 Structural Integrity of Dwelling	I
8.1.2 Shading of Collector	I		
8.1.3 Sensor Location	I	9.2.1 Loads	I
8.2 Mechanical and Electrical Functioning of Dwelling Site	I	9.2.2 Penetration of Structural Members	I
8.2.1 Exhaust and Venting	I		
8.2.2 Utilities	I	9.3 Structural Connections	I
		9.3.1 Structural Connections	I
		9.3.2 Brittle Sub- system	I
		9.3.3 Strength and Stiffness	I
		10.1 Safety of Dwelling and Site	I

TABLE I (CONTINUED)

RESIDENTIAL SYSTEMS, INTERIM PERFORMANCE CRITERIA SUMMARY			
		Sheet <u>7</u> of <u>7</u>	
<u>APPLICATION</u>		<u>TYPE SYSTEMS</u>	
A - APPLICABLE TO SYSTEMS INDICATED		H - HEATING	
I - APPLICABLE TO SYSTEM AND BUILDING		HC - HEATING AND COOLING	
NA - NOT APPLICABLE		HW - HOT WATER ONLY	
RESIDENTIAL INTERIM PERFORMANCE CRITERIA PARAGRAPH	TYPE SYSTEM H	RESIDENTIAL INTERIM PERFORMANCE CRITERIA PARAGRAPH	TYPE SYSTEM H
10.1.1 Fire	I	12.2.1 Accessibility	I
10.1.2 Accidents	I	12.2.2 Ice Dams	I
11.1 Durability	I	12.3 Connections	I
11.1.1 Vegetation	I	12.3.1 Accessibility	I
11.2 Durability and Reliability of Dwelling and Site	I	13.1 Visual Character- istics of Dwelling and Site	I
11.2.1 Chemical Corrosion	A	13.1.1 Dwelling	I
11.2.2 Heat and Moisture	I	13.1.2 Neighborhood	I
11.2.3 Exterior Penetra- tions	I		
11.3 Durability and Reliability of Connections	A		
11.3.1 Material Compatibility	A		
12.1 Maintainability of H, HC, HW Systems	I		
12.1.1 Accessibility	I		
12.1.2 Misuse	I		
12.1.3 Permanent Maintenance Accessories	I		
12.2 Maintainability of Dwelling and Site	I	ORIGINAL PAGE IS OF POOR QUALITY	

6.0 GOVERNMENT DIRECTED REQUIREMENTS

The following requirements are specified in NAS8-32036 and by verbal direction from the contract officer;

(a) IBM shall deliver two identical systems of the following type:

- Single Family Building
- Solar Space Heating and Domestic Hot Water
- Direct Air System (Air Collector)
- Electric Furnace or Heat Pump Auxiliary

(b) All hardware and subsystems, except collectors, and the Rho Sigma differential thermostat shall be purchased by IBM to good commercial practices as off-the-shelf hardware.

(c) Collector and pebble bed sizing may be adjusted for each specific site.

7.0 GEOGRAPHICAL AREA

This heating and hot water system is designed for a single family residence located in the United States. Areas of application include all regions of the U.S. except the extreme north, and regions with low heating degree days, such as Southern California and Florida.

7.1 Typical Geographical Locations

The system design accommodates variation in insolation and heating degree day ranges as follows:

Mean Daily Insolation (Typical Winter Mean)	625 to 1475 BTU/Ft ²
Yearly Heating Degree Days	2000 to 6500

Typical Standard Metropolitan Statistical Areas (SMSA's) within these ranges are:

- Nashville, TN
- Salt Lake City, Utah
- Kansas City, MO
- Los Angeles, CA
- Atlanta, GA
- Las Vegas, NV
- Boston, MA
- Charleston, SC
- Pittsburg, PA
- Detroit, MI
- Wichita, KA
- El Paso, TX

The system application may be extended to other geographical ranges, however, to achieve the optimum performance air handler capacity and/or duct sizes may be impacted.

APPENDIX A

A-0 SYSTEM IDENTIFICATION

This Appendix defines the performance configuration and installation drawings for JIMS Prototype Heating and Hot Water System, IBM Corporation, System Model Number 1A.

A-1 SYSTEM PERFORMANCE SHEETS

Site -

The system shall be installed in a small business office in the city of Huntsville, county of Madison, state of Alabama. This location has a design daily average insolation (typical winter mean) of 770 BTU/Ft² and 3300 heating degree (°F) days (typical annual).

Heating Capacity

The system will provide solar energy for 58 percent of the total heating load during the heating season based on an average annual heating load of 65.8×10^6 BTU and a peak heating load of 41,250 BTU/Hr.

Cooling Capacity

The system will provide solar energy for N/A percent of the average total cooling during the cooling season, based on an average total cooling load of N/A BTU/Month and a peak cooling load of N/A BTU/Hr.

ORIGINAL PAGE IS
OF POOR QUALITY

18:07

Auxiliary Energy

The average annual rate of auxiliary energy supplied to the heating and hot water load shall be no greater than 31.8×10^6 BTU. This shall be no greater than 42 percent of the total energy required for heating and hot water. The average rate of auxiliary energy used for cooling during the cooling season shall be no greater than N/A BTU/Month. This shall be no greater than N/A percent of the total energy required for cooling.

Hot Water

Fifty-two gallons of potable (or usable) hot water shall be delivered at no less than 1.2 gal/min at temperatures no less than 140°F. Recovery time shall be no greater than 0.9 hours. The average hot water heating load will be 0.9×10^6 BTU/Month of which 43 percent is provided by auxiliary energy.

Operating Requirements

The maximum electrical energy required to drive the solar portion of the system at its rated capacity shall be no greater than 1.0 K.W. The maximum electrical energy required to drive the complete system shall be no greater than 28 K.W. The average yearly electrical energy required to drive the system shall be no greater than 6700 K.W.H. Water requirements for cooling condensers and/or air humidification shall be no greater than N/A gal/hr.

Physical Data - Table III

The following subsystems shall have:

	<u>Design life no less than</u>	<u>Weight (filled) no greater than</u>	<u>Installation* dimensions</u>
Heating	<u>20</u> years	<u>N/A</u> lbs	_____
Cooling	<u>N/A</u> years	<u>N/A</u> lbs	_____
Auxiliary Energy	<u>20</u> years	<u>600</u> lbs	_____
Storage	<u>20</u> years	<u>50000</u> lbs	_____
Potable Water (or usable)	<u>10</u> years	<u>1500</u> lbs	_____
Collector	<u>20</u> years	<u>2000</u> lbs	_____
Energy Transport	<u>20</u> years	<u>130</u> lbs	_____
Controls	<u>20</u> years	<u>40</u> lbs	_____

*See Installation Drawings

ORIGINAL PAGE IS
OF POOR QUALITY

DWG NO.
7933609

REVISIONS

CHK	ENGRG NOTICE	LTR	DESCRIPTION	DATE	APPROVED
-----	--------------	-----	-------------	------	----------

ORIGINAL PAGE 12
OF POOR QUALITY

CONTR NO.		INTERNATIONAL BUSINESS MACHINES CORP. FEDERAL SYSTEMS DIVISION HUNTSVILLE, ALA. 35807		
PREPARATION <i>D. S. Sinton 10/29/76</i>		TITLE COLLECTOR SUBSYSTEM SPECIFICATION		
DSGN CHK <i>M. A. Hickland 11-4-76</i>				
DWG CHK				
DSGN APPROVAL <i>J. Cracke 11-4-76</i>		SIZE A	CODE IDENT NO. 20234	DWG NO. 7933609
		SCALE	WT	SHEET

1.0 SCOPE

1.1 This specification describes the design and fabrication requirements for the System 1A Collection Subsystem.

2.0 APPLICABLE DOCUMENTS

2.1 The following documents form a part of this specification unless otherwise specified herein:

Interim Performance Criteria for Solar Heating and Combined Heating/Cooling Systems and Dwellings, January 1, 1976, U. S. Department of Housing and Urban Development.

Intermediate Minimum Property Standards for Solar Heating and Domestic Hot Water Systems, NBSIR 76-1059, April 1976.

3.0 REQUIREMENTS

3.1 General. The collector subsystem shall be designed and fabricated in accordance with the requirements of the applicable documents of 2.1 and the requirements as specified herein. The collector subsystem as shown in Figures 1 and 2 consists of the following items:

Solar Collectors

Feeder Ducts

Manifold Ducts

Installation Hardware

ORIGINAL PAGE IS
OF POOR QUALITY

3.1.1 Fire safety. All materials used to install and insulate the collector subsystem shall meet the fire hazard requirements of the IPC. Materials shall have a flame-spread rating not over 25 and a smoke developed rating not higher than 50 per ASTM E84, UL 733. Duct tape shall not be more combustible than approved flame proofed fabric.

3.1.2 Toxic materials. All materials used to install and insulate the collector subsystem shall not emit toxic gases when exposed to temperature up to 250°F.

3.1.3 Corrosion. Materials used to install and insulate the collector subsystem shall be selected so that their performance will not be affected by corrosion over the 20 year life of the system.

3.1.4 Thermal environment. Materials used to install and insulate the collector subsystem shall be capable of withstanding temperatures from -10 to 250°F without deterioration.

3.2 Solar collectors. Model EF212 solar collectors manufactured by Solar Energy Products Company shall be government furnished. The quantity of collectors is site dependent and shall be as specified in the particular system installation drawing. Collectors shall be mounted to rafters. The rafters shall be boxed-in to provide support for the collector on all four sides. The plane of the collector mounting flange shall face south ± 5 degrees and shall be inclined to the horizontal at an angle which is equal to the sum of the site latitude plus 10 degrees with a tolerance of ± 5 degrees. Collector installation shall be such as to preclude roof leakage.

Appendix A may be used as an installation design guide.

3.3 Feeder ducts. The feeder ducts shall connect the collectors to the inlet and outlet manifold ducts. The feeder ducts shall be 6 inches in diameter and shall be installed in such a manner that the joints at the collector and the manifold duct can be visually inspected. The lengths of the inlet and return feeder ducts shall be made equal and be as short as practical to balance air flow to collectors and minimize head loss.

3.4 Manifold ducts. Groups of collectors shall be manifolded together for parallel air flow with an air flow volumetric flow variation between collectors in any one group being less than 5 percent. When more than one set of manifold ducts (inlet and outlet) are used to service the collectors, air flow shall be proportioned so that the volumetric flow variation between any two collectors in the overall system is less than 10 percent. The maximum average air velocity through any portion of the manifold ducts shall be 600 FPM.

3.5 Duct interfaces. The collector-feeder duct, feeder duct-manifold duct and manifold duct-main duct interfaces shall be designed to minimize air leakage and head losses. Duct tape and sealants shall be used where necessary to minimize air leakage.

3.5.1 Collector-feeder duct interface. The attachment hardware shall be used at the collector-feeder duct interface so that mechanical stresses are distributed away from the openings in the collector to the back side of the collector. The attachment hardware shall not protrude into the collector beyond the rear inside surface of the collector and it shall also insure that the feeder duct does not protrude beyond this surface.

3.5.2 Feeder duct-manifold duct interface. The 6 inch duct take-offs used at the feeder duct-manifold duct interface shall minimize head loss and air leakage.

3.6 Insulation.

3.6.1 Collector insulation. The back side of the collector in the area formed by the boxed-in rafters shall be insulated with a material having a $R = 10.5$ (3 1/2 inch fiber glass, 1 #/ft³ or equivalent).

3.6.2 Duct insulation. Feeder and manifold ducts shall be insulated with a material having a $R = 16.5$ (5 1/2 inch fiber glass, 1 #/ft³ or equivalent).

3.7 Installation hardware.

3.7.1 Duct hangers. Manifold ducts shall be suitably installed with hangers to minimize stresses within the ducts and at duct joints to prevent separation and leakage. Feeder ducts shall also be supported with hangers if attachments at the collector and manifold ducts are not adequate to preclude separation and leakage.

3.7.2 Duct sealing material. All duct joints and interfaces shall be tight. Duct tape or suitable sealant shall be applied at joints to eliminate leakage.

3.7.3 Collector mounting hardware. Collectors shall be secured to rafters and close-outs with 2 inch long No. 10 round head or pan head wood screws or equivalent. Screws shall be suitably spaced to secure the collectors to the roof and maintain the seal between collectors. Mounting screws shall be selected and installed so as to minimize electrochemical corrosion.

3.7.4 Insulation attachment hardware. Collector insulation shall be attached to the ducting with staples, tape and/or straps so that the insulation will be kept in contact with the ducting throughout the life of the system. The insulation shall not be excessively compressed so as to lower the thermal resistance of the insulation.

3.7.5 Flashings. Flashing material shall be selected so as to minimize corrosion when exposed to weather and when in contact with the collector where electrochemical corrosion is possible.

3.7.6 Sealant. A non-hardening sealant shall be used to maintain a water-tight seal between collector flanges and between collector flanges and flashings. A sealant/adhesive shall also be used at the collector-feeder duct interface to bond interface hardware to the collector.

APPENDIX A


A. PREPARATION OF THE ROOF

1. Trusses or rafters must be located on 24" centers. The length of rafters or trusses must be greater than 12 feet.
2. The length of the rough opening required for each solar panel is 144".
3. Material of the same cross-section of the rafter is nailed in place between the rafters at each end to form a rough opening box.
4. Sheathing is applied to the remaining area of the roof. Strips of sheathing must be nailed along the top of the rafters where the panels are to be located. This forms a flush mounting surface all around the SOLORON panel.
5. Roofing felt is applied to cover the sheathing up to the panel opening.
6. Apply roof shingles to the lower portion of the roof up to within 2-3" of the lower edge of the rough opening.
7. Nail in place, in a bed of roofing cement, or high quality non-hardening sealant, aluminum flashing along the entire lower edge of the rough opening.


B. SETTING AND SEALING THE PANELS

1. Apply a non-hardening sealant bed all around the edge of the first rough opening (either the extreme left or right hand opening).
2. Set the first solar panel in place making sure that there are no gaps in the sealant and that the panel is properly seated.
3. Drill clearance holes for 2 inch No. 10 round or pan head wood screws through aluminum flanges on the bottom and one side of the panel (the left side if the first panel is on the left, the right side if the first panel is on the right). The holes should be located approximately 12" apart on all three sides.
4. Screw down the two sides with 2 inch No. 10 wood screws.
5. Apply high quality non-hardening sealant all around the opening to receive the next panel. Make sure there are no gaps in the sealant especially where the flanges of the adjacent collectors overlap.
6. Drill clearance holes through the overlapping flange and the bottom flanges and screw down the two sides of the collector.
7. Repeat steps 1 through 6 for the remaining collectors.


8. Apply 10" wide aluminum flashing in a bed of roof cement or high quality non-hardening sealant on the top flange of the panels.
9. Drill clearance holes for 2" No. 10 wood screws through the flashing and flange along the top edge of the panels and screw down.
10. Apply roof cement or high quality non-hardening sealant bed along extreme left and right flanges of the panels.
11. Apply roofing shingles right up to the top of the panel along both extreme sides of the panel system.
12. Complete by applying shingling along top edge of the collector up to the ridge of the roof.
13. It may be desirable to check out the leak-tightness of the installation by hosing water over all the collectors and joints.



TYPICAL VIEW SHOWING OPENINGS FOR PANELS & WITH PANELS IN PLACE
SCALE 3/4" = 1'-0"




SECTION B-B
SCALE 6" = 1'-0"



SECTION A-A
SCALE 6" = 1'-0"

USE 1/2" 20-22 ROUND HEAD OR PAN HEAD WOOD SCREWS WITH SEAL UNDER THE HEAD EVERY 12" ON EACH SIDE AND ENDS. DRILL CLEARANCE HOLES THROUGH ALUM. FLANGES WHEN IN PLACE.

SOLAR ENERGY PRODUCTS
121 MILLER ROAD
AVON LAKE, OHIO
INSTALLATION OF MODEL
EF-212 DROP IN SOLAR
AIR HEATER
J. DORRIS - 801575



ORIGINAL PAGE IS
OF POOR QUALITY

Figure 2

S

IBM®

FEDERAL SYSTEMS DIVISION
CODE IDENT 20234 - HUNTSVILLE, AL
CODE IDENT 52088 - MANASSAS VA
CODE IDENT 03640 - OWEGO NY

CONTRACT NO.

CODE
* IDENT

20234 PL 7933609

REVISION

LTR +
DATE 08D

EN NO.

SHEET

01

COLLECTOR SUBSYSTEM

REFERENCE DESIGNATION	QUANTITY REQUIRED	UNIT MEAS	CODE IDENT	DRAWING OR DOCUMENT NO	PART OR IDENTIFYING NO	NOMENCLATURE OR DESCRIPTION
C-10	COMMON TO PART NUMBER 7933609				MODELEFF212	COLLECTOR
	30	01			CSS1	ADAPTER (COLLECTOR TO DUCT)
	60	01			CSS2	ELBOW 90 DEG 6 IN
	60	01			CSS3	DUCT TAKE OFF 6 IN
	AR				CSS4	DUCT ROUND 6 IN
	AR				CSS5	INSULATION R-10.5
	AR				CSS6	INSULATION R-16.5
	AR				CSS7	DUCT HANGARS
	AR				CSS8	DUCT TAPE
	AR				CSS9	SEALANT
	AR				CSS10	ADHESIVE
	AR				CSS11	FLASHING
	AR				CSS12	MANIFOLD DUCT
	AR				CSS13	FOIL TAPE

OF MEASURE CODE

= PIECE EACH
= INCH
= FEET
= CUBIC FOOT
= OUNCE (AVDP)
= OUNCE (TROY)

59 = FLUID OUNCE
66 = CUBIC INCH

SYMBOL CODE (SY): V - VENDOR ITEM. SEE SPECIFICATION OR SOURCE CONTROL DRAWING

PLANNING CODE (PL): K - ALTERNATE ITEM P - BULK MATL (ALL OTHER PL CODES ARE FOR IBM REF ONLY: EG. G - GOVT FURN ITEM J - AS REQD
L - DO NOT FILL N - VENDOR FURN R - REF X - DO NOT GENERATE Z - DUMMY CONNECT)

CHARACTER CODE (CH) A - WITH BILL OF MATL D - WITHOUT BILL OF MATL R - FACTORY REF



DWG NO. 7933610

REVISIONS

CHK	ENGRG NOTICE	LTR	DESCRIPTION	DATE	APPROVED

CONTR NO.		INTERNATIONAL BUSINESS MACHINES CORP.			
PREPARATION		FEDERAL SYSTEMS DIVISION			
DSGN CHK		HUNTSVILLE, ALA. 35807			
DWG CHK		TITLE			
DSGN APPROVAL		ENERGY STORAGE SUBSYSTEM SPECIFICATION			
SIZE		CODE IDENT NO.		DWG NO.	
A		20234		7933610	
SCALE		WT		SHEET	

7933610

1.0 SCOPE

This specification describes the design, fabrication and installation requirements for the System 1 Energy Storage Subsystem which are necessary for proper system performance.

2.0 APPLICABLE DOCUMENTS

The following documents form a part of this specification unless otherwise specified herein:

Interim Performance Criteria Commercial Solar Heating and Combined Heating/Cooling Systems and Facilities

Interim Performance Criteria for Solar Heating and Combined Heating/Cooling Systems and Dwellings

Intermediate Minimum Property Standards for Solar Heating and Domestic Hot Water Systems

3.0 REQUIREMENTS

3.1 GENERAL

The energy storage subsystem shall be designed, fabricated and installed in accordance with the requirements of the Interim Performance Criteria and HUD minimum property standards for Solar Systems and the requirements as specified herein. The energy storage subsystem consists of the following items:

- Pebble bed
- Grating
- Lower plenum chamber and grating support
- Upper plenum chamber
- Container

ORIGINAL PAGE IS
OF POOR QUALITY

3.1.1 Fire Safety. All materials used to install and insulate the energy storage subsystem shall meet the fire hazard requirements of the IPC. Materials shall have a flame-spread rating not over 25 and a smoke developed rating not higher than 50 per ASTM E84, UL 733.

3.1.2 Toxic Materials. All materials used to install and insulate the energy storage subsystem shall not emit toxic gases when exposed to temperature up to 250°F.

3.1.3 Corrosion. Materials used to install and insulate the energy storage subsystem shall be selected so that their performance shall not be affected by corrosion over the 20 year life of the system.

3.1.4 Thermal Environment. Materials used to install and insulate the energy storage subsystem shall be capable of withstanding temperatures from -10 to 250°F without deterioration.

3.2 PEBBLE BED

3.2.1 Pebble Selection

The pebbles used in the bed shall be washed to remove dirt, sand and other foreign matter to insure maximum heat transfer characteristics. The type and size requirements are as follows:

Type: Relatively smooth, rounded pebbles, such as, river stones.

Nominal Size: The mean size of the pebbles shall fall within the range of 1/2 to 2 inches.

Relative Pebble Size: Pebbles of approximately the same size shall be utilized to insure adequate air flow. Relative pebble size variations shall be controlled so that the maximum pressure drop across the bed is not exceeded. (See paragraph 3.2.2.2)

3.2.2 Bed Size. The size of the pebble bed shall be within the architectural constraints of the building and the requirements and limitations identified herein.

3.2.2.1 Thermal Storage Capacity/Volume. The volume of the bed shall be such that the thermal storage capacity is 15 ± 5 BTU/ $^{\circ}\text{F}/\text{Ft}^2$ collector.

Note:

This thermal capacity is equivalent to $3/4 \pm 1/4$ cubic foot of pebbles per square foot of collector area. One cubic foot of pebbles weighs approximately 100 pounds. Each collector panel contains 19.7 square feet of effective area.

3.2.2.2 Bed Dimensions. The height of the pebble bed shall be 5 ft. minimum. Cross-sectional area (lateral dimensions) shall be determined, within the constraints identified, such that the static pressure drop across the pebble bed at nominal air flow rates through the bed shall be a minimum of 0.1 and a maximum of 0.6 inches of water column.

3.3 GRATING

The pebble bed shall rest on a metal grating which shall not allow properly sized pebbles to pass through, shall have strength to support the pebble bed weight, and shall minimize resistance to air flow.

3.4 PLENUM CHAMBERS

Plenum chambers shall be located at the top and bottom of the pebble bed and shall interface directly with the solar system main ductwork. They shall be designed to provide air flow vertically through the pebble bed in either direction. The plenums and inlets shall be designed to minimize air channeling through the pebble bed.

3.5 CONTAINER

The container, in combination with the plenum chambers, shall completely enclose the pebble bed and form an integral structure. Materials and fabrication techniques to be utilized are at the discretion of the builder/designer. House walls may form part or all of the container if structurally adequate.

3.6 PEBBLE BED ACCESS

Access must be provided to the pebble bed such that the pebbles can be inspected or replaced at any time. This access may be provided through the side walls of the container or through the upper plenum chamber.

3.7 INSULATION

Except for the interface with the main system ducts at the top and bottom plenum chambers, the energy storage subsystem shall be completely enclosed with insulation having a value of R11 or greater. This insulation can be mounted on inside or outside surfaces of the container and plenum chambers provided that thermal leakage paths to ambient conditions do not exist. At the interfaces with the solar system ductwork, the energy storage subsystem insulation must mate with the main duct insulation such that thermal leakage paths do not exist.

3.8 AIR AND WATER LEAKAGE

All elements of the energy storage subsystem shall be sealed to prevent air leakage from the air passages to ambient. The subsystem shall also be sealed to prevent ingress of ground water.

3.9 GROWTH OF FUNGI

Components and materials used in the energy storage subsystem shall not promote the growth of fungi, mold or mildew.

3.10 Pressure Drop

The static pressure drop across the Energy Storage Subsystem from inlet duct to exit duct shall be from .1 to .7 inches water column at nominal system flow-rates.

ORIGINAL PAGE IS
OF POOR QUALITY

1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
20
21
22
23
24
25
26
27
28
29
30
31
32
33
34
35
36
37
38
39
40
41
42
43
44
45
46
47
48
49
50
51
52
53
54
55
56
57
58
59
60
61

RTS ST	IBM	FEDERAL SYSTEMS DIVISION CODE IDENT 20234 = HUNTSVILLE, AL CODE IDENT 52088 = MANASSAS, VA CODE IDENT 03640 = OWEGO, NY	CONTRACT NO.	CODE * IDENT 20234	PL 7933610	REVISI
						LTR DATE

ITLE	EN NO	SHEET
ENERGY STORAGE SUBSYSTEM		01

REFERENCE DESIGNATION	QUANTITY REQUIRED	UNIT MEAS	CODE IDENT	DRAWING OR DOCUMENT NO	PART OR IDENTIFYING NO.	NOMENCLATURE OR DESCRIPTION
MS COMMON TO PART NUMBER 7933610	1	01			ESS-1	22 TONS WASHED RIVER STONES
	1	01			ESS-2	PEBBLE BED-REF INST. DWG
	1	01			ESS-3	GRATING-PEF INST. DWG
	1	01			ESS-4	TYPE R-11 (FIBERGLASS OR OTHER)

D-7

ORIGINAL PAGE IS
OF POOR QUALITY

UNIT OF MEASURE CODE
01 = PIECE EACH
11 = INCH
12 = FEET
18 = CUBIC FOOT
31 = OUNCE (AVDP)
35 = OUNCE (TROY)


59 = FLUID OUNCE
66 = CUBIC INCH

SYMBOL CODE (SY): V = VENDOR ITEM. SEE SPECIFICATION OR SOURCE CONTROL DRAWING

PLANNING CODE (PL): K = ALTERNATE ITEM P = BULK MATL (ALL OTHER PL CODES ARE FOR IBM REF ONLY: EG. G = GOVT FURN ITEM J = AS REQ
L = DO NOT FILL N = VENDOR FURN R = REF X = DO NOT GENERATE Z = DUMMY CONNECT)

CHARACTER CODE (CH): A = WITH BILL OF MATL D = WITHOUT BILL OF MATL R = FACTORY REF

RELEASED FOR ASM	QTY	TECHNICAL APPROVAL			SYM	DATE	CHANGE NO	7933611	
7933608	1	ELEC							
		METAL							
		PLASTIC							
								DEVELOPMENT NO	Q/M



THE ENERGY TRANSPORT SUBSYSTEM CONSIST OF A PACKAGED SOLAR AIR HANDLER (IBM 7933623) AND NECESSARY DAMPERS, ACTUATORS, AND BACK DRAFT DAMPERS (INCLUDING IBM 7933625) TO ROUTE THE AIR FLOW FOR THE VARIOUS MODES OF OPERATION.

IBM MATERIAL	NO		MUST CONFORM TO ENG SPEC: 890350			
IBM MATL ALTERNATE	NO					
CASE DEPTH		SCALE	NONE	TOLERANCES UNLESS OTHERWISE NOTED	INCH	mm
HARDNESS				LINEAR ±		
SURFACE				ANGLES ±		
TREATMENT				RADI UNLESS OTHERWISE NOTED		
7933611			EDGE/CORNER BREAKS	OUTSIDE MAX		
A				INSIDE MAX		
			NAME			ENERGY TRANSPORT SUBSYSTEM
			DESIGNER			
			DETAILER			<i>McKerry</i> 11/22/5
			DWG CHK			
			DSGN APPRO			
			CLASSIFICATION			

RTS
ST

IBM®

FEDERAL SYSTEMS DIVISION
CODE IDENT 20234 - HUNTSVILLE AL
CODE IDENT 52088 - MANASSAS VA
CODE IDENT 03640 - OWEGO NY

CONTRACT NO.

* CODE
IDENT

20234 PL 7933611

REVISION

LTR
DATE+
08DE

TITLE

EN NO.

SHEET

ENERGY TRANSPORT SUBSYSTEM

01 OF

REFERENCE DESIGNATION	QUANTITY REQUIRED	UNIT MEAS	CODE IDENT	DRAWING OR DOCUMENT NO.	PART OR IDENTIFYING NO	NOMENCLATURE OR DESCRIPTION	SY
MS COMMON TO PART NUMBER 7933611	2	01			SHB-P-1217-HJR	COHRLASTIC DAMPER	
	1	01			SHB-P-1217-VERT	COHRLASTIC DAMPER	
	1	01			7933623	SOLAR AIR HANDLER	
	1	01			7933625	PARTIAL BACKDRAFT DAMPER	

D-9

ORIGINAL PAGE 11
OF POOR QUALITY

UNIT OF MEASURE CODE


01 - PIECE EACH
11 - INCH
12 - FEET
18 - CUBIC FOOT
31 - OUNCE (AVDP)
35 - OUNCE (TROY)59 - FLUID OUNCE
66 - CUBIC INCH

SYMBOL CODE (SY): V = VENDOR ITEM. SEE SPECIFICATION OR SOURCE CONTROL DRAWING

PLANNING CODE (PL): K = ALTERNATE ITEM P = BULK MATL (ALL OTHER PL CODES ARE FOR IBM REF ONLY; EG. G = GOVT FURN ITEM J = AS REQD
L = DO NOT FILL N = VENDOR FURN R = REF X = DO NOT GENERATE Z = DUMMY CONNECT)

CHARACTER CODE (CH): A = WITH BILL OF MATL O = WITHOUT BILL OF MATL R = FACTORY REF

RELEASED FOR ASM	QTY	TECHNICAL APPROVAL			SYM	DATE	CHANGE NO	7933623	
7933611	1	ELEC							
		METAL						DEVELOPMENT NO	
		PLASTIC						Q/V	



THE AIR HANDLER CONTAINS THE BLOWER, BLOWER MOTOR AND NECESSARY DAMPERS AND ACTUATORS TO ROUTE THE AIR FLOW FOR THE VARIOUS MODES OF OPERATIONS.

AIR HANDLER

SOLAR CONTROL CORP.
MODEL SAM Series 20

THE MOTOR SIZE AND BLOWER SPEED ARE DETERMINED BY THE MAX. LOAD DEMANDS OF THE SYSTEM.(MOTORS ARE SPECIFIED IN TABLE "A".)
ALL 115 VAC WIRING IS TO BE **UL** LISTED.

TABLE "A"

H. P.	MANUFACTURE	STYLE NO.	FRAME TYPE
1/4	WESTINGHOUSE ELECTRIC CORP.	317P002	FH-SC56
1/3	WESTINGHOUSE ELECTRIC CORP.	317P003	FH-SP56
1/2	WESTINGHOUSE ELECTRIC CORP.	317P004	FH-56
3/4	WESTINGHOUSE ELECTRIC CORP.	312P629	FH-B56
1	WESTINGHOUSE ELECTRIC CORP.	311P297	FH-F56

DAMPER MOTORS WILL BE:


DAYTON No. 3M231 WITH MAGNETIC TYPE BRAKE REMOVED.
7 RPM, 1/100 H. P.
0.55 FLA, IMPEDANCE PROTECTED
115 VAC/60 CYCLES, CLOCK-WISE ROTATION (SHAFT END)

IBM MATERIAL	NO		MUST CONFORM TO ENG SPEC: 890350					
IBM MATL ALTERNATE	NO							
CASE DEPTH								
HARDNESS								
SURFACE TREATMENT		 THIRD ANGLE PROJECTION	TOLERANCES UNLESS OTHERWISE NOTED	INCH	mm	NAME	SOLAR AIR HANDLER	
			LINEAR ±			DESIGNER		
			ANGLES ±			DETAILER	<i>J. J. King</i>	12/2/76
			RADI UNLESS OTHERWISE NOTED			DWG CHK		
			EDGE/CORNER BREAKS	OUTSIDE MAX		DSGN APPRO		
				INSIDE MAX		CLASSIFICATION		

7933623

A

RELEASED FOR ASM	QTY	TECHNICAL APPROVAL			SYM	DATE	CHANGE NO	7933625	
7933611	1	ELEC							
		METAL							
		PLASTIC							
								DEVELOPMENT NO	Q



NOTES:

1. ALTER AMERICAN WARMING AND VENTILATING INC. OF TOLEDO, OHIO PART NO. SHB-P-1217 FOR A 18" X 18" DUCT IN ACCORDANCE WITH THIS DRAWING. THIS PART CONTAINS FOUR 4" X 17" FABRIC BLADES AND ONE PARTIAL BLADE (NOT A FULL 4" HIGH)
2. REMOVE ONE (FULL) CENTER BLADE BY CUTTING ALONG THE HINGED EDGE. IF CENTER BLADE IS NOT A FULL BLADE REMOVE THE ADJACENT FULL BLADE (ONE ONLY)


- COMMERCIAL ITEM

IBM MATERIAL NO		 SCALE NONE	MUST CONFORM TO ENG SPEC. 890350			
IBM MATL ALTERNATE NO						
CASE DEPTH		 THIRD ANGLE PROJECTION	TOLERANCES UNLESS OTHERWISE NOTED	INCH	mm	NAME DAMPER, PARTIAL
HARDNESS			LINEAR ±			DESIGNER
SURFACE			ANGLES ±			DETAILER JWP 12/1
TREATMENT			RADI UNLESS OTHERWISE NOTED			DWG CHK J. Sinton 12/2
7933625		 INCH mm	EDGE/CORNER BREAKS	OUTSIDE MAX		DSGN APPRO J. Kreske 12-
A				INSIDE MAX		CLASSIFICATION

RELEASED FOR ASM	QTY	TECHNICAL APPROVAL			SYM	DATE	CHANGE NO	7933612
7933608	1	ELEC						
		METAL						
		PLASTIC						
								DEVELOPMENT NO

AIR FLOW FROM COLLECTORS

WATER SUPPLY



NOTES:

- ALL TANK CONNECTIONS ARE 1/2" MPT
- PUMP CONNECTIONS ARE 1.0" IPT, ELECTRICAL SERVICE FROM INTERFACE CONTROLLER BOX
- HEAT EXCHANGER CONNECTIONS ARE 1.0" MPT
- ALL PIPING IS 1/2" COPPER TUBING OR EQUIVALENT, INSULATED WITH A MIN. R VALUE OF 5.0 ON HOT WATER LINES
- PIPING IN CIRCULATION LOOP CAN NOT EXCEED 60' OF 1/2" COPPER TUBING OR EQUIVALENT
- FLANGE ISOLATION VALVES ARE USED ON INPUT & OUTPUT FROM PUMP

IBM MATERIAL	NO		MUST CONFORM TO ENG SPEC: 890350					
IBM MATL ALTERNATE	NO							
CASE DEPTH		SCALE	NONE	TOLERANCES UNLESS OTHERWISE NOTED	INCH	mm	NAME	HOT WATER
HARDNESS			THIRD ANGLE PROJECTION	LINEAR ±			DESIGNER	M. St. Charles 11-11
SURFACE TREATMENT				ANGLES ±			DETAILER	J. Perry 11-11
		INCH		RADI UNLESS OTHERWISE NOTED			DWG CHK	W. H. 11-11
		mm		EDGE/CORNER BREAKS	OUTSIDE MAX		DSGN APPRO	K. H. 11-11
					INSIDE MAX		CLASSIFICATION	

7933612

A

PARTS LIST	IBM	FEDERAL SYSTEMS DIVISION CODE IDENT 20234-HUNTSVILLE, AL CODE IDENT 52088-MANASSAS, VA CODE IDENT 03640-OWEGO, NY		CONTRACT NO.	CODE IDENT 20234 PL 7933612	REVISION ALTR A DATE 03 APR 78				
		LIST TITLE HOT WATER SUBSYSTEM				EN NO. FN663337S	SHEET 01 OF 01			
ITEM NO.	REFERENCE DESIGNATION	QUANTITY REQUIRED	UNIT MEAS	CODE IDENT	DRAWING OR DOCUMENT NO.	PART OR IDENTIFYING NO.	NOMENCLATURE OR DESCRIPTION	SY	PL	CH
ITEMS COMMON TO PART NUMBER 7933612										
		1	99			HWS1	3/4" COPPER TUBING & FITTINGS	N		D
		2	01			HWS2	BRONZE CUTOFF VALVE	N		D
		1	01			SW2-18-18-8	HALSTEAD MITCHELL HEAT EXCHANGER			O
		1	01			T-113	NIBCO BRONZE GATE VALVE 3/4"			O
		1	01			UC05225	JACKSON STORAGE UNIT			D
		1	01			UP-25-42-SF	GRUNDFOS PUMP, ISOLATION VALVES			D
		1	01			S2GAL	HOT WATER HEATER	N		D

UNIT OF MEASURE CODE

01 = PIECE EACH 59 = FLUID OUNCE

11 = INCH 66 = CUBIC INCH

12 = FEET

16 = CUBIC FOOT

31 = OUNCE (AVDP)

35 = OUNCE (TROY)

SYMBOL CODE (SY): V = VENDOR ITEM, SEE SPECIFICATION OR SOURCE CONTROL DRAWING


PLANNING CODE (PL): K = ALTERNATE ITEM P = BULK MATL (ALL OTHER PL CODES ARE FOR IBM REF ONLY; EG, G = GOVT FURN ITEM
J = AS REQD L = DO NOT FILL N = VENDOR FURN R = REF X = DO NOT GENERATE Z = DUMMY CONNECT)

CHARACTER CODE (CH): A = WITH BILL OF MATL D = WITHOUT BILL OF MATL R = FACTORY REF

IBM FORM NO. 952-6324-2

RELEASED FOR ASM	QTY	TECHNICAL APPROVAL		SYM	DATE	CHANGE NO	SYM	DATE	CHANGE NO	7933613
7933608	1	ELEC			JAN 11, 77	66333 T.C.				DEVELOPMENT NO
		METAL			1003078	663336 L.A.				
		PLASTIC								

ORIGINAL PAGE IS
OF POOR QUALITY



THE CONTROL SUBSYSTEM IS COMPRISED OF THREE FUNCTIONAL UNITS WHICH ARE INTERCONNECTED WITH EACH OTHER AND THE AUX. ENERGY SUBSYS

THE FUNCTIONAL UNITS ARE:

CONTROLLER (AIR TRANSPORT)	SOLAR CONTROL CORP. ZIA MODEL 75-176
CONTROLLER (DIFFERENTIAL TEMPERATURE)	RHO SIGMA MODEL 106
INTERFACE CONTROL BOX	IBM 7933619

NOTES:

- COLLECTOR SENSORS MOUNTED FOR GOOD THERMAL CONTACT AND MAXIMUM EXPOSURE TO AIR FLOW AT EXIT DUCT
- SENSOR MOUNTING BRACKET NOT TO EXCEED 1/16" THICK X 1" LEGS
- TYPICAL ACCESS TO CENTER-LINE OF STORAGE IS AT A LEVEL 6" FROM TOP OF ROCK AND 6" FROM BOTTOM WITH CONDUIT OF 1/2" I.D. MINIMUM

IBM MATERIAL NO		 0 25.4	MUST CONFORM TO ENG SPEC: 890350			IBM		
IBM MATL ALTERNATE NO						CONTROL		
		SCALE NONE	TOLERANCES UNLESS OTHERWISE NOTED		INCH	mm	NAME	SUBSYSTEM
CASE DEPTH		 THIRD ANGLE PROJECTION	LINEAR ±				DESIGNER	W. Scott 11/22/
HARDNESS			ANGLES ±				DETAILER	D. J. Perry 11/20/
SURFACE TREATMENT			RADII UNLESS OTHERWISE NOTED				DWG CHK	W. J. Perry 11/23/
7933613		B	EDGE/CORNER BREAKS	OUTSIDE MAX			DSGN APPRO	W. J. Perry 11/23/
				INSIDE MAX			CLASSIFICATION	


PARTS LIST		IBM		FEDERAL SYSTEMS DIVISION CODE IDENT 20234-HUNTSVILLE, AL CODE IDENT 52088-MANASSAS, VA CODE IDENT 03640-OWEGO, NY		CONTRACT NO.		CODE IDENT 20234 PL 7933613	REVISION LTR A DATE 03 APR 78		
LIST TITLE CONTROL SUBSYSTEM								EN NO. EN65352CA	SHEET 01 OF 01		
ITEM NO.	REFERENCE DESIGNATION	QUANTITY REQUIRED	UNIT MEAS	CODE IDENT	DRAWING OR DOCUMENT NO.	PART OR IDENTIFYING NO.	NOMENCLATURE OR DESCRIPTION		SY	PL	CH
ITEMS COMMON TO PART NUMBER 7933613											
1		1	01			7933624	SOLAR AIR CONTROLLER				D
2		1	01			7933619	SYSTEM1-INTERFACE CONTROL BOX				A
3		1	01			DELTA-T-MOD-106	CONTROLLER (RHO-SIGMA)				D
4		1	01			ELMWOOD-3000	THERMOSWITCH				D
UNIT OF MEASURE CODE 01 = PIECE EACH 11 = INCH 12 = FEET 18 = CUBIC FOOT 31 = OUNCE (AVDP) 35 = OUNCE (TROY)				59 = FLUID OUNCE 65 = CUBIC INCH		SYMBOL CODE (SY): V = VENDOR ITEM, SEE SPECIFICATION OR SOURCE CONTROL DRAWING					
						PLANNING CODE (PL): K = ALTERNATE ITEM P = BULK MATL (ALL OTHER PL CODES ARE FOR IBM REF ONLY; EG, G = GOVT FURN ITEM J = AS REQD L = DO NOT FILL N = VENDOR FURN R = REF X = DO NOT GENERATE Z = DUMMY CONNECT)					
						CHARACTER CODE (CH): A = WITH BILL OF MATL D = WITHOUT BILL OF MATL R = FACTORY REF					

IBM FORM NO. 952-6324-2

D-15

ORIGINAL PAGE IS
OF POOR QUALITY

RELEASED FOR ASM	QTY	TECHNICAL APPROVAL	SYM	DATE	CHANGE NO	SYM	DATE	CHANGE NO	7933608
7933608	1	ELEC							
		METAL							
		PLASTIC							



IBM MATERIAL NO	0 1 2 0 25.4 50.8	MUST CONFORM TO ENG SPEC. 890350	IBM NAME INTERFACE CONTROL B-3 DESIGNER W. B. J. DETAILER W. B. J. DATE OK DEGN APPR W. B. J. CLASSIFICATION
IBM MATL. ALTERNATE NO	SCALE 1/2	TOLERANCES UNLESS OTHERWISE NOTED	
CASE DEPTH	THIRD ANGLE PROJECTION	LINEAR S	
HARDNESS	INCH	ANGLES S	
SURFACE	EDGE/CORNER	RADI UNLESS OTHERWISE NOTED	
TREATMENT	BREAKS	OUTSIDE MAX	
		INSIDE MAX	

61933608

D-17


ORIGINAL PAGE IS
OF POOR QUALITY

PARTS LIST		IBM		FEDERAL SYSTEMS DIVISION CODE IDENT 20334 - HUNTSVILLE, AL CODE IDENT 52088 - MANASSAS, VA CODE IDENT 03640 - OWEGO, NY		CONTRACT NO. Sims		CODE IDENT 20334 PL 7933619		REVISION LTR * DATE 30DEC76	
LIST TITLE SYSTEMS-INTERFACE CONTROL BOX								EN NO.		SHEET 01 OF 01	
ITEM NO.	REFERENCE DESIGNATION	QUANTITY REQUIRED	UNIT MEAS	CODE IDENT	DRAWING OR DOCUMENT NO	PART OR IDENTIFYING NO.	NOMENCLATURE OR DESCRIPTION		SY	PL	CH
ITEMS COMMON TO PART NUMBER 7933619											
1		1	01	00843		A-16N12A	NEMA PANEL ENCLOSURE				D
2		6	01			KIT90-340	TYPE 90 DPDT RELAY				D
3		1	01			MST415N	4PDT SWITCH				D
4		1	01	03640	6080555	MST-115D	SWITCH TOGGLE				D
5		2	01	71785		13-540	540 SERIES TERM BLOCK				D
6		1	01	71785		4-540	540 SERIES TERM BLOCK				D
7		1	01	71785		365-41-04-020	SAFETY SHIELD				D
8		1	01			210884	STUD				D
9		1	01	88360		210893	STUD				D
10		16	01	88360		10170	SCREW 6-32X.25BH				D
11		1	01			7933621	BRACKET				D
12		12	01			M516212-41	SCREW, 8-32				D
13		1	01			RACQ-2863	BOX CONNECTORS				D
14		50	01			OV18-250-C	FEMALE QUICK DISCONNECT TERM.				D
15		50	01			PN16-6R-C	WIRE TERMINAL INSULATED				D
16		50	01			PLT1M-CP	PLASTIC WIRE TIE				D
17		12	12			8816-5	18AWG WIRE-PVC-GRN				P
18		12	12			8816-3	18AWG WIRE-PVC-ORANGE				P
19		12	12			8816-9	18 AWG WIRE-PVC-WHITE				P
20		12	12			8816-2	18 AWG WIRE-PVC-RED				P
21		12	12			8816-6	18 AWG WIRE-PVC-BLUE				P
22		12	12			8816-4	18 AWG WIRE-PVC-YELLOW				P
23		12	12			8816-10	18 AWG WIRE-PVC-BLACK				P
24		1	01			7933622	SCHEMATIC, INTERFACE CONTROL				D


UNIT OF MEASURE CODE 01 - PIECE EACH 11 - INCH 12 - FEET 18 - CUBIC FOOT 31 - OUNCE (AVDP) 35 - OUNCE (TROY)	59 - FLUID OUNCE 66 - CUBIC INCH
--	-------------------------------------

SYMBOL CODE (SY): V - VENDOR ITEM. SEE SPECIFICATION OR SOURCE CONTROL DRAWING	
PLANNING CODE (PL): K - ALTERNATE ITEM P - BULK MATL (ALL OTHER PL CODES ARE FOR IBM REF ONLY: EQ - GOVT FURN ITEM J - AS REQD L - DO NOT FILL N - VENDOR FURN R - REF X - DO NOT GENERATE Z - DUMMY CONNECT)	
CHARACTER CODE (CH): A - WITH BILL OF MATL O - WITHOUT BILL OF MATL R - FACTORY REF	

RELEASED FOR ASM	QTY	TECHNICAL APPROVAL	SYM	DATE	CHANGE NO	SYM	DATE	CHANGE NO	7933620
7933619	1								



CONTROLLER ENCLOSURE
SCALE 1/4



HOLE	NO	SIZE
A	12	8-32 UNC 2B
B	16	6-32 UNC 2B

INTERNAL PANEL
SCALE 1/2

ITEM MATERIAL	NO	0	1	2	3	4	5	6	7	8	9
ITEM MATL ALTERNATE	110	MUST CONFORM TO ENG SPEC 890350									
CASE DEPTH		TOLERANCES UNLESS OTHERWISE NOTED									
HARDNESS		INCH									
SURFACE TREATMENT	PAINT EXTERIOR OF BOX BLUE, KRYLON 1901	.005/.002									
		LINEAR &									
		ANGLES &									
		RADIUS UNLESS OTHERWISE NOTED									
		EDGE/CORNER									
		BREEKE									
		OUTSIDE MAX									
		INSIDE MAX									
		CLASSIFICATION									


7933620-D

NAME	INTERFACER
CONTROL BOX	
DESIGNER	1/2/76
DETAILS	1/2/76
DATE	1/2/76
BY	1/2/76
CLASSIFICATION	

0296661

ORIGINAL PAGE IS
OF POOR QUALITY

RELEASED FOR ASM	QTY	TECHNICAL APPROVAL				SYM	DATE	CHANGE NO	SYM	DATE	CHANGE NO	7933621
7933619	1	ELEC										DEVELOPMENT NO Q/M
		METAL										
		PLASTIC										




7933621-C

IBM MATERIAL NO 6061-T6	0 1 2 0 25.4 50.8 SCALE 1/1	MUST CONFORM TO ENG SPEC: 680350		IBM	
ALUMINUM		TOLERANCES UNLESS OTHERWISE NOTED		NAME BRACKET,	
IBM MATL ALTERNATE NO	THIRD ANGLE PROJECTION	LINEAR ±	±.005/-0.002	INTERFACE CONTROL BOX	
CASE DEPTH		ANGLES ±		DESIGNER	27 DEC 76
HARDNESS		RADII UNLESS OTHERWISE NOTED		DETAILER	28 Dec 76
SURFACE TREATMENT 218 CHROMATE	INCH mm	EDGE/CORNER BREAKS MIN.	OUTSIDE MAX INSIDE MAX	DWG CHK	
17933621 C				DSGN APPRO	28 Dec 76
				CLASSIFICATION	

ORIGINAL PAGE IS
OF POOR QUALITY

RELEASED FOR ARM	7933619	TECHNICAL APPROVAL	SYM	DATE	CHANGE NO	SYM	DATE	CHANGE NO	7933622
		ELEC							
		METAL							
		PLASTIC							
								DEVELOPMENT NO	Q/M



7933622-C

IBM MATERIAL NO		0 1 2	MUST BE USED TO DRAW BY EC: 000350		IBM	
IBM MATL ALTERNATE NO		0 25.4 50.8			NAME SCHEMATIC	
CASE DEPTH		SCALE NONE			INTERFACE CONTROL	
HARDNESS		THIRD ANGLE PROJECTION			DESIGNER 11/17/76	
SURFACE TREATMENT		INCH mm			DETAILER 11/11/76	
					DWG CHK 11/11/76	
					DSGN APPRO 11/12/76	
					CLASSIFICATION	

RELEASED FOR ASM	QTY	TECHNICAL APPROVAL			SYM	DATE	CHANGE NO	793362	
7933613	1	ELEC							
		METAL							DEVELOPMENT NO
		PLASTIC							

THE SOLAR AIR CONTROLLER IS A PACKAGED ELECTRICAL CONTROL SYSTEM.

SOLAR AIR CONTROLLER

ZIA ASSOCIATES, INC.
MODEL 75-176 (FOUR
MODE CONTROLLER)

THE SOLAR AIR CONTROLLER IS TO HAVE:




1. UL LISTED WIRE ABOVE 70 VOLTS.
2. UL LISTED 24V RELAYS. (HONEYWELL R8225D1003 & R8225A1017)
3. CLASS II TRANSFORMER. (HONEYWELL AT74B1004)

STANDARD FEATURES FROM MANUFACTURE ARE:

1. DIFFERENTIAL OFFSET PROGRAMMABLE $10^{\circ} - 60^{\circ} \text{ F.}$
2. HYSTERESIS PROGRAMMABLE $3^{\circ} - 20^{\circ} \text{ F.}$
3. PROGRAMMABLE DELIVERY TEMPERATURE SET $90^{\circ} - 120^{\circ} \text{ F.}$
4. FOR 115 VAC OPERATION.

D-21

ORIGINAL PAGE IS
OF POOR QUALITY

IBM MATERIAL	NO	 SCALE ~	MUST CONFORM TO ENG SPEC: 890350					
IBM MATL ALTERNATE	NO							
CASE DEPTH			TOLERANCES UNLESS OTHERWISE NOTED				NAME	
HARDNESS			INCH	mm	SOLAR AIR CONTROLL			
SURFACE		 THIRD ANGLE PROJECTION	LINEAR $\pm$			DESIGNER	1.5.10.10	12
TREATMENT			ANGLES $\pm$			DETAILER	SW/eng	12
			RADIO UNLESS OTHERWISE NOTED			DWG CHK		
			EDGE/CORNER BREAKS			DSGN APPRO		
7933624			OUTSIDE MAX			CLASSIFICATION		
			INSIDE MAX					

DWG NO.
7933614

REVISIONS

CHK	ENGRG NOTICE	LTR	DESCRIPTION	DATE	APPROVED
	K42-009	--	Release	11/22/76	

The Auxiliary Energy Subsystem provides the necessary energy to supplement the solar system. It is designed to provide the entire heating load in the event solar energy is not available. In addition, the system will provide cooling for summer time operation.

The subsystem consists of a air-to-air split-system heat pump and separate resistance heaters.

The heat pump is sized for the building cooling load. Heating capacity of the heat pump is augmented by the resistance heaters to meet the building heating load at local design temperatures. The resistance heaters are located in the transport system such that the solar heating may also be augmented.

The heat pump and resistance heaters shall be furnished by the building owner.

CONTR NO.		INTERNATIONAL BUSINESS MACHINES CORP. FEDERAL SYSTEMS DIVISION HUNTSVILLE, ALA. 35807			
PREPARATION <i>[Signature]</i> 11-23-76		TITLE AUXILIARY ENERGY SUBSYSTEM			
DSGN CHK <i>[Signature]</i> 11-23-76					
DWG CHK					
DSGN APPROVAL <i>[Signature]</i> 11-22-76		SIZE A	CODE IDENT NO.	DWG NO.	7933614
		SCALE	WT	SHEET	

DWG NO.

7933615

CHK LNDRG NOTICE LTR

REVISIONS

DESCRIPTION

DATE

APPROVED

ORIGINAL PAGE IS
OF POOR QUALITY

ORIGINAL PAGE IS
OF POOR QUALITY

CONTR NO.		INTERNATIONAL BUSINESS MACHINES CORP. FEDERAL SYSTEMS DIVISION HUNTSVILLE, ALA. 35807	
PREPARATION			
DSGN CHK			
DWG CHK			
DSGN APPROVAL <i>[Signature]</i>		TITLE Integration Subsystem Specification	
SIZE A		CODE IDENT NO.	DWG NO. 7933615
SCALE		WT	SHEET

955-1685-0

↑ F-1

1.0 SCOPE

1.1 This specification describes the design, fabrication and installation requirements for the Integration Subsystem of Solar Heating and Hot Water System 1.

2.0 APPLICABLE DOCUMENTS

The following documents form a part of this specification to the extent that they apply to the items of hardware noted herein:

- o Interim Performance Criteria Commercial Solar Heating/Cooling Subsystems and Facilities (hereafter referred to as the IPC)
- o Intermediate Minimum Property Standards for Solar Heating and Domestic Hot Water Systems
- o Local Building, Plumbing, Mechanical, Electrical and Fire Protection Codes
- o Installation Plans and Specifications

3.0 REQUIREMENTS

3.1 General.

The Integration Subsystem consists of the necessary hardware to interconnect the various subsystem components to provide a solar heating and hot water system.

3.1.1 Fire safety. All materials used to install and insulate the collector subsystem shall meet the fire hazard requirements of the IPC. Materials shall have a flame-spread rating not over 25 and a smoke developed rating not higher than 50 per ASTM E84, UL 733. Duct tape shall not be more combustible than approved flame-proofed fabric.

3.1.2 Corrosion. Materials used to install and insulate the collector subsystem shall be selected so that their performance will not be affected by corrosion over the 20-year life of the system.

3.1.4 Thermal environment. Materials used to install and insulate the collector subsystem shall be capable of withstanding temperature from -10°F to 250°F without deterioration.

3.2 Interconnecting Ducts

Within the CFM, velocity and static pressure parameters called for in the System Design Specification, the interconnecting ducts may vary in size as dictated by the availability of space within the building and the size of the connections to the various subsystems serviced by this hardware. However, the installation design shall provide as short a run as practical to minimize friction losses. All duct joints and connections shall be designed to minimize air leakage and shall provide necessary brackets, angles and supporting hardware to minimize stresses on subsystem components.

3.3 Duct Sealing Material

All duct joints and interface with subsystem components shall be sealed with duct tape or suitable sealant to eliminate air leakage.

3.4 Dampers

3.4.1 Back-draft dampers. Four automatic back-draft dampers shall be installed in the duct work to provide for flow control and regulation. Location of these dampers will be in accordance with the system schematic P/N 7933608.

3.4.2 Shut-off dampers. Four manually operated dampers shall be installed within the interconnecting duct work to provide for collector and attic ventilation and isolation of the Pebble Bed Storage unit during summer operation. The attic and outside ventilating units shall have insect screens attached to the damper unit. The damper unit shall be selected on the basis of providing minimum air leakage when closed and pressure drop when open.

3.5 Heat Exchanger

An air-to-water heat exchanger shall be installed in the duct work to provide pre-heat of domestic hot water. Location will be in accordance with system schematic P/N 7933608.

3.6 Duct Insulation

All interconnecting ducts shall be insulated with material having an R value of not less than 16.5.


3.7 Duct Hangers

All interconnecting ducts shall be suitably supported to minimize stresses within the ducts and at duct joints to prevent separation and leakage.

3.8 Filters

An UL approved all metal heavy duty wire mesh commercial filter shall be installed in the inlet duct from the attic ventilation intake. The size and mounting detail shall be incorporated in the system installation drawings.

RELEASED FOR ASM	QTY	TECHNICAL APPROVAL			SYM	DATE	CHANGE NO	7933616	
7933608	1	ELEC							
		METAL							DEVELOPMENT NO
		PLASTIC							



THE DATA COLLECTION SUBSYSTEM CONSISTS OF FIVE ITEMS:

SDAS	P/N 7932922
JUNCTION BOX (J-BOX)	P/N 7933585
CABLES (J-BOX TO SDAS)	P/N 7933578 P/N 7933579-2 P/N 7933583 P/N 7933579-1
SENSORS (AS LISTED ON)	PL 7933616
SENSOR WIRE LIST	W/L 7933616

SENSORS WILL BE DELIVERED AT SITE AS REQUIRED DURING INSTALLATION.

IBM MATERIAL	NO	 SCALE NONE	MUST CONFORM TO ENG SPEC: 890350					
IBM MATL ALTERNATE	NO							
CASE DEPTH								
HARDNESS								
SURFACE TREATMENT		 THIRD ANGLE PROJECTION	TOLERANCES UNLESS OTHERWISE NOTED			NAME	DATA COLLECTI	
			INCH	mm		SUBSYSTEM		
			LINEAR ±			DESIGNER		
			ANGLES ±			DETAILER	JaP	11/2
			RADIO UNLESS OTHERWISE NOTED			DWG CHK		
			EDGE/CORNER BREAKS	OUTSIDE MAX		DSGN APPRO		
				INSIDE MAX		CLASSIFICATION		

PARTS
LIST

IBM

FEDERAL SYSTEMS DIVISION
CODE IDENT 20234 - HUNTSVILLE AL
CODE IDENT 52088 - MANASSAS, VA
CODE IDENT 03640 - OWEGO, NY

CONTRACT NO.

CODE
* IDENT

20234 PL 7933616

REVISION

LTR +
DATE 15 DE

TITLE

EN NO

SHEET

SDC SUBSYSTEM-IBM SYSTEM 1

01 OF

QTY	REFERENCE DESIGNATION	QUANTITY REQUIRED	UNIT MEAS	CODE IDENT	DRAWING OR DOCUMENT NO.	PART OR IDENTIFYING NO.	NOMENCLATURE OR DESCRIPTION	SY
	ITEMS COMMON TO PART NUMBER	7933616						
		AR				DC340	THERMAL TRANSFER GREASE	
		AR				DC96-080	ADHESIVE	
		20	01			F102-4	WEATHERHEAD	
		17	01			F132	FITTING	
		5	01			F203U28	THERMOWELL	
		1	01			IS4	RADIATION SHIELD	
		2	01			MKV-3/4-J07	FLOWMETER	
		1	01			PC5-1F	WATTMETER	
		1	01			PC5-19F	WATTMETER	
		1	01			PC5-2F	WATTMETER	
		1	01			PC5-28F	WATTMETER	
		1	01			PC5-29F	WATTMETER	
		1	01			PC5-32F	WATTMETER	
		1	01			PYRANOMETER	PYRANOMETER, PRECISION	
		2	01			S53P55Z36	SINGLE ELEMENT PROBE	
		3	01			S53P700Z36	SINGLE ELEMENT PROBE	
		7	01			S53P85Z36	SINGLE ELEMENT PROBE	
		3	01			S57P55Z36	DUAL ELEMENT PROBE	
		5	01			S57P85Z36	DUAL ELEMENT PROBE	
		2	01			430-2	FLOW PROBE	
		1	01			7932922	SDCS UNIT ASSY 47 CH	
		1	01			7933585	J-BOX (32 CHAN) SDAS INTERFACE	

UNIT OF MEASURE CODE

01 - PIECE EACH

11 - INCH

12 - FEET

18 - CUBIC FOOT

31 - OUNCE (AVDP)

35 - OUNCE (TROY)

59 - FLUID OUNCE

66 - CUBIC INCH

SYMBOL CODE (SY): V - VENDOR ITEM. SEE SPECIFICATION OR SOURCE CONTROL DRAWING

PLANNING CODE (PL): K - ALTERNATE ITEM P - BULK MATL (ALL OTHER PL CODES ARE FOR IBM REF ONLY: EG. G - GOVT FURN ITEM J - AS REQ
L - DO NOT FILL N - VENDOR FURN R - REF X - DO NOT GENERATE Z - DUMMY CONNECT)

CHARACTER CODE (CH): A - WITH BILL OF MATL D - WITHOUT BILL OF MATL R - FACTORY REF

REVISIONS

CHK	ENGRG NOTICE	LTR	DESCRIPTION	DATE	APPROVED
R	66348NW	H	REPLACE PAGE 1-SEE EN. REV PAGE 7-COL 7. REV PAGE 8-COL 9. REV PAGE 13-COL 7 DEFINITION. REV PAGE 14-COL 9 DEFINITION. REV PAGE 17-REV SCHEMATIC. REV PAGE 22-CHANGE TD & T QUANTITIES. REV PAGE 23 to 28-CHANGE TDs to Ts,& ADD T COEFFICIENTS. CHANGE T RANGES AND MICRO-BOARDS. CHANGE LIQUID FLOW RANGES & ADD PAGE 29.	2/6/8	<i>[Signature]</i>

Approved and Baselined CCBd 301-78-0281 dated *3/6/78*

ORIGINAL PAGE IS
OF POOR QUALITY

CONTR NO. NAS 8-32036		INTERNATIONAL BUSINESS MACHINES CORP.	
PREPARATION <i>L.H. Jensen</i>		FEDERAL SYSTEMS DIVISION	
DSGN CHK		HUNTSVILLE, ALABAMA 35807	
DWG CHK		TITLE	
DSGN APPROVAL		INSTRUMENTATION PROGRAM-	
		IBM SYSTEM 1 A	
SIZE	CODE IDENT NO.	DWG NO.	
A	20234	-IP-7933616	
SCALE	WT	SHEET 1 of 29	

INTRODUCTION

THIS DOCUMENT DEFINES AND CONTROLS THE MEASURING REQUIREMENTS AND INSTRUMENTATION SYSTEM APPLICATIONS FOR A SOLAR HEATING AND COOLING OPERATIONAL SITE.

THE SECTIONS OF THIS DOCUMENT ARE DESCRIBED AS FOLLOWS:

1. PREAMBLE SECTION — CONTAINS DESCRIPTIONS, EXPLANATIONS, INSTRUCTIONS AND DIAGRAMS NECESSARY TO UNDERSTAND THIS DOCUMENT AND THE APPLICATION OF THE DATA COLLECTION SYSTEM TO A SPECIFIC SITE.
2. INSTRUMENTATION COMPONENTS SECTION — LISTS ALL HARDWARE ELEMENTS OF THE DATA COLLECTION EQUIPMENT NOT SUBSEQUENTLY LISTED IN THE MEASUREMENTS SECTION.
3. MEASUREMENTS SECTION — LISTS ALL MEASUREMENTS WHICH ORIGINATE IN A SOLAR HEATING AND COOLING OPERATIONAL SITE WITH APPROPRIATE INFORMATION FOR EACH MEASUREMENT.

INSTRUMENTATION PROGRAM AND COMPONENTS LIST ---

IBM SYSTEM 1A

IP 7933616

4/25/77

REV _____

TABLE OF CONTENTS

	<u>PAGE</u>
APPROVAL/REVISION SHEET	1
INTRODUCTION	2
TABLE OF CONTENTS	3
PREAMBLE SECTION	4
INSTRUMENTATION COMPONENTS SECTION	19
MEASUREMENTS SECTION	21

INSTRUMENTATION PROGRAM AND COMPONENTS LIST --- IBM SYSTEM 1A

4/25/77

IP 7933616

REV

PREAMBLE SECTION

C-6

INSTRUMENTATION PROGRAM AND COMPONENTS LIST: IBM SYSTEM 1A
IP 7933616

8/9/77
REV A

OPERATIONAL SITE IDENTIFICATION

1. SITE NAME: IBM SYSTEM 1A
2. PON: NA
3. SITE NUMBER: 0004
4. SITE SDAS TELEPHONE NUMBER: 205-536-0236
5. SITE SDAS COMPUTER ADDRESS: 021
6. SITE ADDRESS: 2809 BURKE ROAD, S.W. (PARALLEL ACCESS OFF TRIANA)
7. LOCATION: HUNTSVILLE, ALA
8. SYSTEM DESIGNER: IBM CORPORATION
9. SYSTEM TYPE: HEATING/HOT WATER
10. FLUID MEDIA: AIR

G-7

ORIGINAL PAGE IS
OF POOR QUALITY

INSTRUMENTATION PROGRAM AND COMPONENTS LIST:

IBM SYSTEM 1A

IP7933616

11/7/77

REV D

ASSOCIATED DOCUMENTS

1. SOLAR HEATING AND COOLING INSTRUMENTATION INSTALLATION GUIDELINES, OCTOBER 1, 1977.
2. [X] SITE DATA ACQUISITION SUBSYSTEM PERFORMANCE SPECIFICATION, MAY 14, 1976, IBM NO. 7932905.
[] SITE DATA ACQUISITION SUBSYSTEM MODEL II, PERFORMANCE SPECIFICATION, 7934354.
[] SITE DATA ACQUISITION PERFORMANCE SPECIFICATION. ACUREX MODEL.
3. CENTRAL DATA PROCESSING SOFTWARE PERFORMANCE SPECIFICATION, JULY 28, 1976, IBM NO. 7933251.
4. THERMAL DATA REQUIREMENTS AND PERFORMANCE EVALUATION PROCEDURES FOR THE NATIONAL SOLAR HEATING AND COOLING DEMONSTRATION PROGRAM, AUGUST, 1976 (NBSIR 76-1137).
5. JUNCTION BOX PERFORMANCE SPECIFICATION, OCTOBER 26, 1976, IBM NO. 7933446.
6. ON SITE MONITOR (OSM) OPERATION MANUAL, OCTOBER 17, 1977, IBM NO. 7934365.

G-8

ORIGINAL PAGE IS
OF POOR QUALITY

INSTRUMENTATION PROGRAM AND COMPONENTS LIST:

IBM SYSTEM 1A

IP 7933616

1/25/78

REV H

MEASUREMENTS LEGEND

THE LEGEND FOR THE DATA LISTED IN THE MEASUREMENTS SECTION OF THIS DOCUMENT IS AS FOLLOWS:

COLUMN 1	COLUMN 2	COLUMN 3	COLUMN 4	COLUMN 5	COLUMN 6	COLUMN 7
LINE	MEAS NUMBER OSM CODE	MEASUREMENT NAME	CHANNEL #	ASYN	# WIRES	OPERATING RANGE SENSOR OUTPUT SDAS GAIN ACTUAL OPER RANGE

G-9

ORIGINAL PAGE IS
OF POOR QUALITY

MEASUREMENTS LEGEND (CONTINUED)

G-10

COLUMN 8				COLUMN 9				COLUMN 10				COLUMN 11			
MICROBRD TYPE				TEMP SERIAL #				SENSOR TYPE				NOTES			
MICROBRD P/N				SCALE FACTOR UNITS				SENSOR MANUFACT				SERIAL #			
SENSOR EXCIT				CDPS SCALE FACTOR				SENSOR P/N				CROSS SECTION AREA			
				(A1,A2,A3,A0)				WELL P/N							

THE COLUMN HEADINGS ARE DEFINED ON THE FOLLOWING SHEETS.

COLUMN 1. LINE NUMBER

THIS COLUMN IS USED FOR AUTOMATIC PRINTOUT DATA CONTROL AND LINE IDENTIFICATION.

COLUMN 2. (MULTIPLE DATA SETS)

THIS COLUMN CONTAINS TWO DATA SETS AS DEFINED BELOW:

MEAS NUMBER. THE FIRST LINE OF THIS COLUMN LISTS EACH MEASUREMENT WHICH IS IDENTIFIED BY A UNIQUE ALPHANUMERIC CODE CONSISTING OF TEN CHARACTERS AS FOLLOWS:

FIELD NO.	1	2	3	4
MEASUREMENT NO.	XY	001	-	0001

PARAMETER TYPE _____

PARAMETER SEQUENCE _____

SEPARATOR _____

SITE IDENTIFIER _____

AN ASTERISK (*) FOLLOWING THE MEASUREMENT NUMBER DENOTES A CHANGE FROM THE PREVIOUS RELEASE.

OSM CODE. THE SECOND LINE OF THIS COLUMN LISTS THE ON SITE MONITOR SWITCH SETTING TO DISPLAY ENGINEERING UNIT DATA. THIS IS TO BE USED WITH ASSOCIATED DOCUMENT 6 AND THE GENERAL NOTES ON PAGE 16 OF THIS DOCUMENT.

ORIGINAL PAGE IS
OF POOR QUALITY

C-11

INSTRUMENTATION PROGRAM AND COMPONENTS LIST --- IBM SYSTEM 1A
IP 7933616

8/9/77

REV A

A. FIELD NO. 1 - PARAMETER TYPE

CODE	PARAMETER	UNITS	ABB
D D	WIND DIRECTION SWITCH	DEGREES - AZIMUTH DEGREES - ON/OFF	DEG DEG
EP	ELECTRICAL POWER	KILOWATTS	KW
F F	FLOWRATE (NATURAL GAS) FLOWRATE (FUEL OIL)	FEET ³ /MINUTE GAL/MINUTE	SCFM GPM
I	SOLAR FLUX	BTU PER FOOT ² X HOUR	BTU/FT ² - HR
RH	HUMIDITY	PERCENT	PER
SP	SPARE	N/A	N/A
T	TEMPERATURE	DEGREES FAHRENHEIT	DEG F
TD	DIFFERENTIAL TEMPERATURE	DEGREES FAHRENHEIT	DEG F/DT
W W	FLOWRATE (LIQUID) FLOWRATE (AIR)	GALLONS PER MINUTE, CUBIC FEET PER MINUTE	GPM CFM
V	WIND SPEED	MILES PER HOUR	MPH
PD	DIFFERENTIAL PRESSURE	POUNDS PER SQ. INCH	PSI

G-12

B. FIELD NO. 2 - PARAMETER SEQUENCE

A NUMERIC GROUPING WHICH DESIGNATES THE SEQUENTIAL NUMBER OF A MEASUREMENT WITHIN EACH SUBSYSTEM. THE SEQUENTIAL NUMBER OF EACH MEASUREMENT CONFORMS TO THE PATTERN ESTABLISHED IN FIGURE 3-1 OF SHC-1006. SEQUENTIAL NUMBER ALLOCATIONS ARE AS FOLLOWS:

<u>NUMERIC SEQUENCE</u>	<u>SUBSYSTEM</u>
001-099	CLIMATOLOGICAL
100-199	COLLECTOR
200-299	THERMAL STORAGE
300-399	DOMESTIC HOT WATER
400-499	SPACE HEATING
500-599	SPACE COOLING
600-699	BUILDING/LOAD

C. FIELD NO. 3 - SEPARATOR

FOR NUMERIC CLARITY.

D. FIELD NO. 4 - SITE IDENTIFIER

A NUMERIC GROUPING WHICH DESIGNATES THE SITE IN WHICH THE MEASUREMENT IS LOCATED.

COLUMN 3. MEASUREMENT NAME

THIS COLUMN LISTS THE MEASUREMENT NAME USED TO DESCRIBE THE DATA SOURCE.

COLUMN 4. CHANNEL #

THIS COLUMN DEFINES THE SDAS CHANNEL ASSIGNED TO EACH MEASUREMENT (2 - 48). CHANNEL 1 IS RESERVED FOR AN SDAS INTERNAL CALIBRATION OFFSET MEASUREMENT.

COLUMN 5. ASYN

THIS COLUMN DEFINES EACH MEASUREMENT WHICH IS ASYNCHRONOUSLY SAMPLED AND IS INDICATED BY THE LETTER "A". THESE MEASUREMENTS ARE SAMPLED EACH 32 SECONDS WITH THE AVERAGED VALUE PER 5 MINUTES MAINTAINED FOR TRANSMISSION. SYNCHRONOUSLY SAMPLED MEASUREMENTS ARE READ ONCE PER 5 MINUTES AND ARE IDENTIFIED BY THE "-" SYMBOL.

COLUMN 6. # WIRES

THIS COLUMN DEFINES THE NUMBER OF WIRES PER CHANNEL USED IN THE SDAS. EITHER 3 WIRE OR 2 WIRE CHANNELS ARE AVAILABLE VIA A PRE-DEFINED CONFIGURATION.

INSTRUMENTATION PROGRAM AND COMPONENTS LIST:

IBM SYSTEM 1A

IP 7933616

1/25/78

REV H

COLUMN 7. (MULTIPLE DATA SETS)

THIS COLUMN CONTAINS FOUR DATA SETS AS DEFINED BELOW:

OPERATING RANGE - THE FIRST LINE OF THIS COLUMN DESCRIBES THE OPERATING RANGE OF THE PARAMETER IN ENGINEERING UNITS.

SENSOR OUTPUT RANGE - THE SECOND LINE OF THIS COLUMN DESCRIBES THE OUTPUT RANGE IN VOLTS OF THE SENSOR.

SDAS GAIN - THE THIRD LINE OF THIS COLUMN DESCRIBES THE SDAS GAIN SELECTED FOR EACH CHANNEL.

ACTUAL OPER RANGE - THE FOURTH LINE OF THIS COLUMN IS APPLICABLE TO ABSOLUTE TEMPERATURES ONLY (AFTER CORRECTION COEFFICIENTS ARE APPLIED.)

COLUMN 8. (MULTIPLE DATA SETS)

THIS COLUMN CONTAINS THREE DATA SETS AS DEFINED BELOW:

MICROBRD TYPE - THE FIRST LINE OF THIS COLUMN DESCRIBES THE TYPE OF MICROBOARD USED FOR SIGNAL CONDITIONING OF THE EMPLOYED SDAS CHANNEL.

MICROBRD P/N - THE SECOND LINE OF THIS COLUMN DESCRIBES THE PART NUMBER OF THE MICROBOARD USED FOR SIGNAL CONDITIONING OF THE EMPLOYED SDAS CHANNEL. A MCN-DEFINED MICROBOARD P/N INDICATES THAT THIS CHANNEL SHARES A MICROBOARD WITH ANOTHER CHANNEL WHICH WILL DEFINE THE P/N.

SENSOR EXCIT - THE THIRD LINE OF THIS COLUMN DESCRIBES THE EXCITATION REQUIREMENTS FOR EACH SENSOR, IF REQUIRED.

COLUMN 9. (MULTIPLE DATA SETS)

THIS COLUMN CONTAINS THREE DATA SETS AS DEFINED BELOW:

TEMP SERIAL #- THE FIRST LINE OF THIS COLUMN DESCRIBES THE TEMPERATURE PROBE SERIAL NUMBER (IF AVAILABLE).

SCALE FACTOR UNITS - THE SECOND LINE OF THIS COLUMN DESCRIBES THE ENGINEERING UNITS MAINTAINED IN THE CDPS FOR EACH MEASUREMENT.

CDPS SCALE FACTOR -- THE THIRD AND FOURTH LINES OF THIS COLUMN DESCRIBE THE NUMERIC SCALE FACTOR(S) USED IN THE CENTRAL DATA PROCESSING SYSTEM (CDPS) TO CONVERT EACH MEASUREMENT TO ENGINEERING UNITS.

COLUMN 10. (MULTIPLE DATA SETS)

THIS COLUMN CONTAINS FOUR DATA SETS AS DEFINED BELOW:

SENSOR TYPE - THE FIRST LINE OF THIS COLUMN LISTS THE TYPE (NAME) OF THE EMPLOYED SENSOR.

SENSOR MANUFACT - THE SECOND LINE OF THIS COLUMN LISTS THE SENSOR MANUFACTURER.

SENSOR P/N - THE THIRD LINE OF THIS COLUMN LISTS THE PART NUMBER OF THE SENSOR.

WELL P/N - THE FOURTH LINE OF THIS COLUMN DESCRIBES THE PART NUMBER OF A THERMAL WELL IF REQUIRED FOR THE DEFINED SENSOR.

INSTRUMENTATION PROGRAM AND COMPONENTS LIST --- IBM SYSTEM 1A

4/25/77

IP 7933616

REV _____

COLUMN 11. (MULTIPLE DATA SETS)

NOTES - THE FIRST LINE OF THIS COLUMN DEFINES ANY INFORMATION REQUIRED TO SUPPORT CLARIFICATION OF THE MEASUREMENT.

SERIAL # - THE SECOND LINE OF THIS COLUMN DEFINES AN ITEM UNIQUE SERIAL NUMBER MARKED BY THE MANUFACTURER.

CROSS SECTION AREA - THE THIRD LINE OF THIS COLUMN DEFINES THE CROSS SECTIONAL AREA OF A DUCT IN SQUARE FEET.

G-17

ORIGINAL PAGE IS
OF POOR QUALITY

INSTRUMENTATION PROGRAM AND COMPONENTS LIST:

IBM SYSTEM 1A

IP 7933616

1/25/78

REV II

GENERAL NOTES

NOTE 1 - DATA NOT CURRENTLY DEFINED.

NOTE 2 - ENGINEERING UNIT VALUES MUST BE CALCULATED USING COUNTS & SCALE FACTORS.


NOTE 3 - LIQUID FLOW WITHIN $\pm 5\%$ OF DISPLAYED VALUE.

NOTE 4 - INSULATION WITHIN ± 5 BTU OF DISPLAYED VALUE.

NOTE 5 - POWER MEASUREMENT RANGE VALUES & SCALE FACTORS ARE HALVED DUE TO FOUR TURNS THRU TRANSFORMERS.

G-18

IBM SYSTEM 1A INSTRUMENTATION SCHEMATIC




4/25/77

REV

IP 7933616

INSTRUMENTATION PROGRAM AND COMPONENTS LIST --- IBM SYSTEM 1A

18



DATA COLLECTION SYSTEM

INSTRUMENTATION PROGRAM AND COMPONENTS LIST --- IBM SYSTEM 1A
IP 7933616

4/25/77

REV

INSTRUMENTATION COMPONENTS SECTION

C-21

ORIGINAL PAGE IS
OF POOR QUALITY

INSTRUMENTATION PROGRAM AND COMPONENTS LIST --- IBM SYSTEM 1A
IP 7933616

8/9/77
REV A

<u>EQUIPMENT NAME</u>	<u>PART NUMBER</u>	<u>SERIAL NUMBER</u>
-----------------------	--------------------	----------------------

JUNCTION BOX

7933575

009

CABLES (J-BOX TO SDAS)

NO. 1

7933579-1

NO. 2

7933583

NO. 3

7933579-2

NO. 4

7933579-3

NO. 5

7933578

SDAS

7932922

007

N/A

N/A

IBM DRAWING NUMBER

7933616

G-22

ORIGINAL PAGE IS
OF POOR QUALITY

INSTRUMENTATION PROGRAM AND COMPONENTS LIST --- IBM SYSTEM 1A

IP 7933616

4/25/77

REV

MEASUREMENTS SECTION

G-23

INSTRUMENTATION PROGRAM AND COMPONENTS LIST ---

IBM SYSTEM 1A

2/1/78

IP 7933616

REV H

MEASUREMENT SUMMARY

<u>PARAMETER</u>	<u>NUMBER</u>
WIND DIRECTION/SWITCH	---/ 2
ELECTRICAL POWER	7
FLOWRATE (NATURAL GAS)	---
SOLAR FLUX	1
HUMIDITY	---
SPARE	(2)
TEMPERATURE /SPECIAL MEASUREMENTS	27/3
DIFFERENTIAL TEMPERATURE	--
FLOWRATE (LIQUID/AIR)	5
WIND SPEED	---
TOTAL	46

G-24

ORIGINAL PAGE IS
OF POOR QUALITY

REPORT BY CHANNEL ASSIGNMENT

LINE	MEAS NUMBER	MEASUREMENT	C	A	#	OPERATING RANGE	MICROBRD TYPE	TEMP SERIAL #	SENSOR TYPE	NOTES
LINE	ISM CODE	NAME	#	N	F	ACTUAL OPER RANGE	SENSOR EXCIT	SCALE FACTOR UNITS	SENSOR MANUFACT	SERIAL #
LINE	ISM CODE	NAME	#	N	F	ACTUAL OPER RANGE	SENSOR EXCIT	(A1,A2,A3,A0)	WELL P/N	CROSS SECTION AREA
1	T150 -0004*	COLLECTOR APPAY	02	-	3	30/230 DEGF	BRIDGE		PRT	(TD100)
2		OUTLET TEMP				0-100 MV	7932988	DEGF/BIT	MINCO	
3	0202					50		+1940204E-07	553P85	
4						+32.316 /+239.81		+0004525E-09		
5								+0001793E-13		
6								+3231644E-05		
7	FP101-0004	AIR HANDLER	03	A	2	0-1.5 KW	STRAIGHT		WATT XDCR	
8		POWER				0-50 MV	7932985	KW/BIT	OHIO SCIENTIFONICS	
9	0342					50		+0029294E-07	PC5-19	
10										
11	T301 -0004*	DHW MAKEUP TEMP	04	-	3	30/160 DEGF	BRIDGE		PRT	
12						0-100 MV	7932990	DEGF/BIT	MINCO	
13	0401					50		+1256871E-07	553P85736	
14						+31.591 /+162.47		+0002145E-09	F203060	
15								+0005294E-14		
16								+3159161E-05		
17	FP300-0004	DHW ELECTRIC	05	A	2	0/1.5 KW	STRAIGHT		WATT XDCR	
18		POWER				0-50 MV	7932985	KW/BIT	OHIO SCIENTIFONICS	
19	0542					50		+0029294E-07	PC5-19F	
20										
21	T353 -0004*	DHW TANK	06	-	3	30/160 DEGF	BRIDGE		PRT	(TD303)
22		OUTLET TEMP				0-100 MV	7932990	DEGF/BIT	MINCO	
23	0601					50		+1256605E-07	553P85736	
24						+31.411 /+162.05		+0002137E-09	F203060	
25								+0005368E-14		
26								+3141120E-05		
27	T001 -0004*	SOLAR FLUX	07	A	2	0/383.22 BTU/FT2-HR	CAPACITOR		PYN ONOM	
28						0-12 MV	7934363	B/E2-H/BIT	EXPLEY	15220F3
29	0724					50		3.1136294	PSP	
30										
31	T301 -0004*	DHW PREHEAT TNE	08	-	3	30/160 DEGF	BRIDGE		PRT	
32		OUTLET TEMP				0-100 MV	7932990	DEGF/BIT	MINCO	
33	0701					50		+1254442E-07	553P110236	
34						+31.818 /+162.46		+0002144E-09	F203080	
35								+0005020E-14		
36								+3181873E-05		
37	SP001-0004	SPACE	09	-	2	N/A	SHORT		N/A	
38						N/A	7932938	N/A	N/A	
39						50		N/A	N/A	
40										
41										

ORIGINAL PAGE IS
OF POOR QUALITY

REPORT BY CHANNEL ASSIGNMENT

L	MEASUREMENT	C	A	H	OPERATING RANGE	MICROBRD TYPE	TEMP SERIAL #	SENSOR TYPE	NOTES
1	MEASUREMENT	A	S	I	SENSOR OUTPUT RANGE	MICROBRD P/N	SCALE FACTOR UNITS	SENSOR MANUFACT	SERIAL #
2	CSM CODE	H	N	T	ACTUAL OPER RANGE	SENSOR EXCIT	CPUS SCALE FACTORS	SENSOR P/N	CROSS SECTION AREA
1	T151 -0004* ROCK STORAGE	10	-	3	30/230 DIG	BRIDGE		PRT	(TD101)
2					0-100 MV	7932983	DEGF/RT	MINCO	
3	1002				50		+1087641E-07	553P55	
4					+33.135 /+241.43		+0004540E-09		
5							+0001721E-13		
6							+3313404E-05		
7	EP400-0004 STRIP HEATER	11	-	2	0-20 K	STRAIGHT		WATT XDCP	
8					0-50 MV	7932985	KW/RT	UNIT SEMITRONICS	
9	1147				50		+0393625E-07	PLS-32	
10									
11	T350 -0004* HW PREHEAT COIL	12	-	3	30/160 DEGF	BRIDGE		PRT	(TD300)
12					0-100 MV	7932990	DEGF/RT	MINCO	
13	1201				50		+1253641E-07	553P55	
14					+31.637 /+162.17		+0002140E-09	F20302A	
15							+0005035E-14		
16							+3163722E-05		
17	K100 -0004 COLLECTOR ARRAY	13	-	2	0-1250 FPM	STRAIGHT		ANEMOMETER	
18					0-5 V	7932985	CFM/RT	SUPRA	
19	1381				1	115 VAC	+3205754E-07	430-2	2.222
20							+0008194E-07		
21							+0001450E-09		
22	T351 -0004* HW PREHEAT TANK	14	-	3	30/160 DEGF	BRIDGE		PRT	(TD301)
23					0-100 MV	7932990	DEGF/RT	MINCO	
24	1401				50		+1254205E-07	553P55	
25					+31.320 /+161.92		+0002142E-09	F20302A	
26							+0005000E-14		
27							+3132088E-05		
28	E100 -0004 ATTIC VENT MODE	15	-	2	0/1 DIG	STRAIGHT		SKY VANE	
29					0-5 V	7932985	DEGF/RT	WEATHER MEASURE	
30	1540				1	+5 VDC	1074.	W101-P-DC560	
31							0.		
32							0.		
33	T352 -0004* HW TANK	16	-	3	30/160 DEGF	BRIDGE		PRT	(TD302)
34					0-100 MV	7932990	DEGF/RT	MINCO	
35	1601				50		+1252331E-07	553P55	
36					+31.186 /+161.58		+0002133E-09	F20302B	
37							+0005216E-14		
38							+3118628E-05		

C-26

REPORT BY CHANNEL ASSIGNMENT

L N E	MEAS NUMBER CSM CODE	MEASUREMENT NAME	C H #	A S I #	W Y R #	OPERATING RANGE SENSOR OUTPUT RANGE SCALE GAIN ACTUAL RPPD RANGE	MICROPPD TYPE MICROPPD P/N SENSOR EXCIT	TEMP SERIAL # SCALE FACTOR UNITS CPDS SCALE FACTORS (A1,A2,A3,A0)	SENSOR TYPE SENSOR MANUFACT SENSOR P/N WILL P/N	NOTES SERIAL # CROSS SECTION AREA
1 2 3 4	6301-0004*	EDW TAKEUP FLOW	17	-	2	0/6.78 GPM 0-10 MV 50	STRAIGHT 7932985 +5 VDC	GPM/BLT +6709266E-07 SOCT	FLOW METER RAMAPO MNV-3/4-J07	S/N4520
5 6 7 8 9 0	1450-0004*	SOLAR HEATING OUTLET TEMP	18	-	3	30/23.0 DEGF 0-100 MV 50 +31.632 /+239.43	BRIDGE 7932988	DEGF/BLT +1982527E-07 +0004542E-09 +0001714E-13 +3168280E-05	PRT MINCO S53P85	(TD400)
11 12 13 14	FP401-0004	DUCT HEATER POWER	19	-	2	0-20 KW 0-50 MV 50	STRAIGHT 7932985	KW/BLT +0340625E-07	WATT XOCB CHLO SEMITRONICS PC5-32F	
15 16 17 18 19 20	1451-0004*	SOLAR AUX OUTLET TEMP	20	-	3	30/23.0 DEGF 0-100 MV 50 +32.477 /+240.27	BRIDGE 7932988	DEGF/BLT +1982527E-07 +0004542E-09 +0001714E-13 +3249794E-05	PRT MINCO S53P85	(TD401)
21 22 23 24	6306-0004*	EDW SOLAR TANK FLOW	21	-	2	0/2.00 GPM 0-10 MV 50	STRAIGHT 7932985 +5 VDC	GPM/BLT +2954834E-07 SOCT	FLOW METER RAMAPO MNV-3/4-J07	S/N4519
25 26 27 28 29 30	1452-0004*	AUX RETURN AIP TEMP	22	-	3	30/16.0 DEGF 0-100 MV 50 +31.729 /+161.80	BRIDGE 7932990	DEGF/BLT +1249217E-07 +0002124E-09 +0005032E-14 +3172942E-05	PRT MINCO S53P150236	(TD402)
31 32 33 34	SM602-0004*	SDAS 5V SUPPLY	23	-	2	0/5.5 VOLTS 0-5 V 1	BRIDGE 7932939	VOLTS/BLT 0.+.0053763		(D990)
35 36 37 38 39 40	1101-0004*	OUTSIDE AMBIENT TEMP	24	-	3	-20/12.0 DEGF 0-100 MV 50 -19.912 /+121.47	BRIDGE 7932986	DEGF/BLT +1356782E-07 +0002412E-09 +0006350E-14 -1991241E-05	PRT MINCO S53P85	

ORIGINAL PAGE IS
OF POOR QUALITY

REPORT P2 CHANNEL ASSIGNMENT

LINE	CHAS NUMBER	MEASUREMENT	C H A N N E L	A S S I G N M E N T	OPERATING RANGE SENSOR OUTPUT RANGE SOAS GAIN ACTUAL OPER RANGE	MICROPRO TYPE MICROPRO P/N SENSOR XCIT	TEMP SERIAL # SCALE FACTOR UNITS CPDS SCALE FACTORS (A1,A2,A3,A0)	SENSOR TYPE SENSOR MANUFACT SENSOR P/N WILL P/N	NOTES SERIAL # CROSS SECTION AREA
1	W303-0004	OHM MAKEUP	25	2	0-100 GAL	STRAIGHT			
2		FLOW			0-5 V	7932985	GAL/BLT		
3	NOTE 2				1	+5 VDC	.0977517		
5	1100-0004*	COLLECTOR ARRAY	26	3	30-240 DEGE	BRIDGE			
6		INLET TEMP			0-100 MV	7932988	DEGE/BLT	PRT	
7	2602				50		+1975435E-07	MINCO	
8							+0004508E-09	S53P85	
9							+0001609E-13		
10							+3154864E-05		
11	SP008-0004	SPACE	27	2	N/A	SHORT		N/A	
12					N/A	7932938	N/A	N/A	
13					50		N/A		
16	1101-0004*	ROCK STORAGE	28	3	30-240 DEGE	BRIDGE			
17		OUT/IN TEMP			0-100 MV	7932988	DEGE/BLT	PRT	
18	2802				50		+1986881E-07	MINCO	
19							+0004568E-09	S53P85	
20							+0001724E-13		
21							+3023109E-05		
22	18403-0004	HEAT PUMP	29	A 2	0-10 KW	STRAIGHT			
23		CUMULISS PWR			0-50 PV	7932985	KW/BLT	WAT-XUCR	
24	2946				50		+0195312E-07	OHIO SEMITRONICS	
25								PC5-29	
26	1102-0004*	MIDDLE COLL ARS	30	3	30-450 DEGE	BRIDGE			
27		SUP-TEMP(MID)			0-100 MV	7932987	DEGE/BLT	PRT	
28	3003				50		+3915971E-07	MINCO	
29							+0001609E-09	S32A	
30							+0001179E-12		
31							+3199876E-05		
32	C400-0004	SUMMER OPER	31	2	0-1 DEG	STRAIGHT			
33		MODE (SWITCH)			0-5 V	7932985	DEG/BLT	SKY VANE	
34	4130				1	+5 VDC	1024	WEATHER MEASURE	
35							0.	W101-P-DC540	
36							0.		
37	1103-0004*	MIDDLE COLL ARS	32	3	30-450 DEGE	BRIDGE			
38		SUP-TEMP(UP)			0-100 PV	7932987	DEGE/BLT	PRT	
39	3203				50		+3915971E-07	MINCO	
40							+0001499E-09	S32A	
41							+0001179E-12		
42							+3199876E-05		

C-28

REPORT BY CHANNEL ASSIGNMENT

L N F	MEAS NUMBER RSM CODE	MEASUREMENT NAME	C H A N N E L	#	OPERATING RANGE SENSOR OUTPUT RANGE SDAS GAIN ACTUAL OPER RANGE	MICROBRO TYPE MICROBRO P/N SENSOR FACIT	TEMP SERIAL # SCALE FACTOR UNITS CPSS SCALE FACTORS [A1,A2,A3,A0]	SENSOR TYPE SENSOR MANUFACT SENSOR P/N WELL P/N	NOTES SERIAL # CROSS SECTION AREA
1	EP301-0004	CHW CIRCULATING	33	A 2	0-5 KW	STRAIGHT		WATT XDCR	
2		PUMP POWER			0-50 MV	7932985	KW/BIT	OHIO SEMITRONICS	
3	3340				50		+7009765E-07	PC5-1	
5	TC00-0004*	INSIDE AMBIENT	34	- 3	30-160 DEGF	BRIDGE		PRT	
6		TEMP			0-100 MV	7932990	DEGF/BIT	MINCO	
7	3401				50		+1260515E-07	553P85	
8					+33.392 /+1.4.67		+0002154E-09		
9							+0005692E-14		
11	TP402-0004	CIRCULATING FAN	35	A 2	0-1 KW	STRAIGHT		WATT XDCR	
12		POWER			0-50 MV	7932985	KW/BIT	OHIO SEMITRONICS	
13	3541				50		+0019531E-07	PC5-2	
15	TI04-0004*	MIDDLE COLL ABS	36	- 3	30-450 DEGF	BRIDGE		PRT	
16		SUR-TEMP (LCW)			0-100 MV	7932987	DEGF/BIT	MINCO	
17	3603				50		+3915971E-07	532A	
18					+31.999 /+449.55		+0001499E-08		
19							+0001179E-12		
20							+3199976E-05		
21	SM600-0004*	SDAS S/C#1 15V	37	- 2	0/15.5 VOLTS	BRIDGE			(D991)
22					0-5 MV	7932939	VOLTS/BIT		
23	3730				1		0.+0151515		
25	TI05-0004*	MIDDLE COLL ABS	38	- 3	30-450 DEGF	BRIDGE		PRT	
26		SUR-TEMP (SCF)			0-100 MV	7932987	DEGF/BIT	MINCO	
27	3803				50		+3915971E-07	532A	
28					+31.999 /+449.55		+0001499E-08		
29							+0001179E-12		
30							+3199976E-05		
31	SM601-0004*	SDAS S/C#2 15V	39	- 2	0/15.5 VOLTS	BRIDGE			(D992)
32					0-5 V	7932939	VOLTS/BIT		
33					1		0.+0151515		
35	TI00-0004*	ROCK STORAGE	40	- 3	30-160 DEGF	BRIDGE		PRT	
36		TEMP - TOP			0-100 MV	7932990	DEGF/BIT	MINCO	
37	4001				50		+1233001E-07	553P700	
38					+32.000 /+110.35		+0002069E-09		
39							+0004839E-14		
40							+3199993E-05		

ORIGINAL PAGE IS
OF POOR QUALITY

REPORT BY CHANNEL ASSIGNMENT

L I N E	MEAS NUMBER	MEASUREMENT	C H A N N E L	#	OPERATING RANGE	MICROHARD TYPE	TEMP SERIAL #	SENSOR TYPE	NOTES
	CEM CODE	NAME	N	N	SENSOR OUTPUT RANGE	MICROHARD R/R/N	SCALE FACTOR UNITS	SENSOR MANUFACT	SERIAL #
					ACTUAL D/P/R RANGE	SENSOR EXCIT	(A1,A2,A3,A0)	WILL P/R	CROSS SECTION AREA
1	W400-0004	AIR DUCT OUTLET	41	2	0-1250 FPM	STRAIGHT		ANEMOMETER	
2		FLUX			0-5 V	7932985	CEM/BIT	SILVERA	
3	41R1			1		115 VAC	+2005114E-07	430-2	2.007
4							+0007400E-07		
5							+0001318E-09		
6	1201-0004*	ROCK STORAGE	42	3	30-160 DEGF	BRIDGE		PRT	
7		TEMP - MIDDLE			0-100 MV	7932990	DEGF/BIT	MINCO	
8	4201			50			+1233001E-07	553P700	
9					+32.000 /+160.35		+0002969E-09		
10							+0004836E-14		
11							+3199993E-05		
12	1202-0004*	ROCK STORAGE	43	3	30-160 DEGF	BRIDGE		PRT	
13		TEMP - BOTTOM			0-100 MV	7932990	DEGF/BIT	MINCO	
14	4301			50			+1233001E-07	553P700	
15					+32.000 /+160.35		+0002969E-09		
16							+0004836E-14		
17							+3199993E-05		
18	1203-0004*	ATTIC TEMP	44	3	30-160 DEGF	BRIDGE		PRT	
19					0-100 MV	7932990	DEGF/BIT	MINCO	
20	4401			50			+1263402E-07	553P85	
21					+32.000 /+164.57		+0002167E-09		
22							+0005331E-14		
23							+3299920E-05		
24	1300-0004*	HW PREHEAT PUMP	45	3	30-160 DEGF	BRIDGE		PRT	
25		INLET TEMP			0-100 MV	7932990	DEGF/BIT	MINCO	
26	4501			50			+1261745E-07	557P55	
27					+31.636 /+163.04		+0002173E-09	1203028	
28							+0004912E-14		
29							+3163675E-05		
30	1401-0004*	COLD WATER	46	3	30-160 DEGF	BRIDGE		PRT	
31		SUPPLY TEMP			0-100 MV	7932990	DEGF/BIT	MINCO	
32	4601			50			+1261898E-07	557P55	
33					+32.115 /+163.55		+0002165E-07	1203028	
34							+0005251E-14		
35							+3213576E-05		
36	1400-0004*	SOLAR RETURN	47	3	30-160 DEGF	BRIDGE		PRT	
37		AIR TEMP			0-100 MV	7932990	DEGF/BIT	MINCO	
38	4701			50			+1257735E-07	557P85	
39					+31.000 /+162.97		+0002164E-09		
40							+0004274E-14		
41							+3199985E-05		

C-30

REPORT BY CHANNEL ASSIGNMENT

L	M	F	MEAS NUMBER	MEASUREMENT NAME	C H A N S I N #	# W I T H Y R E	OPERATING RANGE	SENSOR OUTPUT RANGE	MICROBRD TYPE	TEMP SERIAL #	SENSOR TYPE	NOTES
			CSH CODE				SCALE GAIN	MICROBRD P/N	CPDS SCALE FACTORS		SENSOR MANUFACT	SERIAL #
							ACTUAL GPR RANGE	SENSOR EXCIT	(A1,A2,A3,A0)		WELL P/N	CROSS SECTION AREA
1			T402 -0004*	SPACE HEATING	4R	- 3	30/160 DEGE	BRIDGE			POT	
2				INLET TEMP			0-100 MV	7932990	DEGE/BLT		MINCO	
3			4801				50		+1255597E-07		557P85	
4							+32.561 /+163.29		+0002140E-09			
5									+0005245E-14			
6									+3256160E-05			

G-31

ORIGINAL PAGE IS
OF POOR QUALITY

DWG NO. 7933445

REVISIONS

CHK	ENGRG NOTICE	LTR	DESCRIPTION	DATE	APPROVED

DCN-1

Revision B
Date: February 11, 1977

CDRL Item No.s - 2a
-13

ORIGINAL PAGE IS
OF POOR QUALITY

CONTR NO. NAS8-32036		INTERNATIONAL BUSINESS MACHINES CORP. FEDERAL SYSTEMS DIVISION HUNTSVILLE, ALA. 35807	
PREPARATION <i>J.G. Daniel</i>	TITLE Verification Plan/Procedure for Prototype Solar Energy Heating and Hot Water System Model No. 1		
DSGN CHK			
DWG CHK			
DSGN APPROVAL <i>V.H. Johnson</i>	SIZE A	CODE IDENT NO.	DWG NO. 7933445
	SCALE	WT	SHEET

1.0 PURPOSE

- 1.1 The purpose of this document is to present the plan/procedure for verifying the requirements of Performance Specification for prototype solar energy heating and hot water system model number 1.

2.0 SCOPE

- 2.1 This document describes the plan/procedure for performing prototype systems verification and includes development, qualification, and acceptance verification. One system of each design shall be physically tested in accordance with this document. All subsequent systems shall be verified by analysis, similarity and inspections.

3.0 APPLICABLE DOCUMENTS

The following documents form a part of this plan to the extent specified herein:

- o Interim Performance Criteria for Solar Heating and Combined Heating/Cooling Systems and Dwellings, HUD - January 1, 1975
- o Performance Specification for Prototype Heating and Hot Water System Model No. 1.

4.0 VERIFICATION APPROACH

- 4.1 Prototype system verification to the requirements of the system performance specification and interim performance criteria will be accomplished in three verification phases--development, qualification, and acceptance. The verification methods utilized for system verification will be similarity, analysis, inspection, demonstration and test.

Prototype system verification will commence with a detailed analysis of all system hardware, components, and subsystems and progress through system evaluation and testing. Figure I of this plan depicts a summary flow for system verification.

A detailed system test procedure for performing the test requirements of this document will be prepared and submitted to MSFC for review and approval. This procedure will describe the methods and procedures for conducting prototype system test on the MSFC system test breadboard facility.

Following completion of verification program, a final system verification report will be prepared and submitted to MSFC. Report will contain all information pertinent to system verification.

5.0 DEVELOPMENT VERIFICATION REQUIREMENTS

5.1 Hardware/Component/Subsystem Verification - All hardware, components and subsystems that comprise the prototype system shall be verified to be in accordance with the requirements of the prototype system performance specification and the interim performance criteria. Verification of hardware, components, and subsystems will be accomplished by engineering analysis, similarity, inspection, demonstration and/or testing methods.

Subsystem test evaluation will be conducted on the system collectors, controller, and data acquisition system. All other prototype system subsystems, hardware and components will be verified individually by analysis and/or during prototype system verification.

5.2 System Development Verification - Development verification will be conducted on prototype system M/N 1 to ensure that system will perform to the requirements of the system performance specification and interim performance criteria. Development verification will consist of the following:

- o Analysis of hardware, component, and subsystem evaluation data for compliance to system performance specification and interim performance criteria requirements.
- o Analysis of system design for compliance to system performance specification and interim performance criteria requirements.
- o System testing on MSFC System Test Breadboard Facility. Tests to be conducted are as follows:
 - System operational functional test
 - System capacity for control, energy storage, and distribution to load at known simulated energy inputs.
 - System capacity for control, energy collection, storage, and distribution to load at outside ambient weather conditions.

5.2.1 System Operational Functional Test. A system operational functional test shall be conducted on prototype system M/N 1. Operational functional test shall consist of the following:

- Operational test of system blowers
- Operational test of system damper valves
- System check for air leaks
- Measurement of flow rate and pressure drop across collectors
- Measurement of flow rate and head pressure of each blower in each system operational mode

- Operational test of domestic hot water subsystem
(operation of pump, valves, controller)
- Pressure test of domestic hot water subsystem

5.2.1.1 System Operational Functional Test Procedure

- (a) Install prototype system on breadboard test stand in accordance with test setup schematics and system drawings and verify that simulated transport ducting sizes and lengths are the same as those identified in the prototype system test procedures.
- (b) Make appropriate electrical connections to prototype system air handler, blowers, controller and hot water subsystem. Connections shall be made in accordance with system drawings and shall contain a quick disconnect.
- (c) Connect hot water subsystem to city water supply and fill domestic hot water tank, preheat tank, and water lines.
- (d) Pressurize hot water subsystem to 150 psi and check for leaks. Special emphasis shall be placed on leak testing soldered joints and mechanical connections. There shall be no leaks.
- (e) Activate system blower and manually override system controller to provide air flow through collectors to system storage and back through collectors.
- (f) Check system for air leaks and exercise effort to make system air tight as practical. Leaks on collectors shall be sealed with butyl tape and duct leaks with duct tape.

- (g) During operational mode of step (e) measure flow rate and pressure drop across collectors and storage.
Nominal flow rate for collectors should be 1200 ± 150 cfm.
Nominal flow rate for storage should be 1200 ± 150 cfm.
Nominal pressure drop across collectors should be $.08 \pm .01$ "H₂O.
Nominal pressure drop across storage should be $.18 \pm .06$ "H₂O.
- (h) Manually override system controller to provide air flow through collectors and system load loop (bypass storage) and return to collectors.
- (i) During operational mode of step (h) measure flow rate and pressure drop across collectors and load loop.
Nominal flow rate for collectors should be 1200 ± 150 cfm.
Nominal flow rate for load loop should be 1200 ± 150 cfm.
Nominal pressure drop across collectors should be $.08 \pm .01$ "H₂O.
Nominal pressure drop across load loop should be $.2 \pm .1$ "H₂O.
- (j) Check load loop and air handler for air leaks and repair any leaks noted.
- (k) Manually override system controller to provide air flow from storage to load loop and return to storage.
- (l) During operational mode of step (k) measure flow rate and pressure drop across storage.
Nominal flow rate should be 1200 ± 150 cfm.
Nominal pressure drop should be $.18 \pm .06$ "H₂O.

5.2.2 System Test with Simulated Energy Inputs. Prototype system M/N 1 shall be tested to evaluate system capacity for control, storage and distribution to load using controlled simulated energy inputs. Tests shall be performed with simulated energy inputs of 90, 100, 125, 150 and 175°F. Simulated temperatures shall be controlled in the duct area that simulates

ORIGINAL PAGE IS
OF POOR QUALITY

collector outlet as close as practical. Each simulated temperature shall be circulated throughout the system a sufficient amount of time until the system has stabilized at the simulated temperature level. The following evaluations shall be made during system test.

- (a) Time required to raise storage to each simulated temperature level from temperature level of storage at the start of test (temperature vs. time in hours).
- (b) Time required to exhaust storage to load to 80°F from each simulated temperature level (temperature vs. time in hours).
- (c) BTU supplied to load from storage at each simulated temperature level (Btu/hour vs. time in hours).
- (d) Btu supplied to hot water system from simulation at each simulated temperature level (Btu/hour vs. time in hours).

5.2.2.1 Procedure for System Test with Simulated Energy Inputs

Prototype system M/N 1 shall be installed on MSFC test breadboard in accordance with system test schematics and system drawings and subjected to system test using controlled simulated energy inputs. Test shall be conducted with simulated energy inputs of 90, 100, 125, 150 and 175°F. Simulated temperatures shall be controlled in the duct area that simulates collector output as close as practical. Tests shall be conducted as follows:

- (a) Place system collector inlet and outlet dampers in the closed position (isolating collectors from system). Set energy simulator to maintain 90°F.
- (b) Manually override system controller and allow air to circulate from breadboard energy simulator through system air handler and ducting to storage and return to energy simulator. Allow circulation in this mode until temperature stabilization has occurred throughout the system.

(c) Measure and record the following conditions.

- Temperature drop across system (from simulation to storage)
- Time required to raise and stabilize storage temperature to simulation temperature from temperature level of storage at the start of test (temperature vs. time in hours).

(d) Following completion of step (c) manually override system controller and allow air to circulate from storage through air handler and ducting to breadboard load device. Set load device to maintain 70°F and 1200 ± 150 CFM.

(e) Measure and record the following conditions.

- Temperature drop from storage to load
- Btu supplied to load from storage (Btu vs. time in hours)
- Time required to exhaust storage to 80°F (temperature vs. time in hours)

(f) Following completion of step (e) manually override system controller and make ducting connection to allow air circulation from simulator through air handler over hot water preheat coil and return to simulator. Apply power to system blower.

(g) Measure and record Btu supplied to domestic hot water system (Btu vs. time in hours). Test for approximately four hours at each simulated temperature level (constant load for hot water system to be supplied from breadboard).

PRECEDING PAGE BLANK NOT FILMED
H-9

PRECEDING PAGE BLANK NOT FILMED

- (h) Repeat steps (b) through (g) at each of the following simulation temperatures: 100, 125, 150, and 175°F.

5.2.3 System Test at Outside Weather Conditions. Prototype system

M/N 1 shall be tested to evaluate system capacity for control, energy collection, storage, and distribution to load at outside ambient weather conditions.

Prototype system M/N 1 shall be tested at outside weather conditions the maximum number of days possible contingent on system delivery schedule and breadboard facility work load. Primary intent of this test is to obtain as much data as possible prior to installing system at demonstration site. The following evaluations shall be made during system testing at outside weather conditions.

- (a) Complete records of weather data. (Solar radiation, ambient temperature, wind speed and direction, relative humidity, and cloud cover.) (Weather measurements vs. time of day.)
- (b) Total energy collected by solar system per day (Btu vs. time in hours).
- (c) Total energy supplied to load per day.
 - Direct from collectors (Btu vs. time of day)
 - From storage (Btu vs. time of day)
- (d) Total energy supplied to hot water subsystem per day (Btu vs. time of day)
- (e) Power required to operate solar system per day (watts vs. time of day)
- (f) System control functions. (Manual observations).

- (g) System data collection functions (Compare with breadboard instrumentation)

5.2.3.1 Procedure for System Test at Outside Weather Conditions

Prototype system M/N 1 shall be installed on MSFC test breadboard in accordance with system test schematics and system drawings and subjected to system test at outside weather conditions. Test shall be conducted as follows:

- (a) Configure the system collectors, storage, air handler, controller, hot water subsystem, and simulated ducting in an active mode and connect system to breadboard load device. (System configuration to simulate actual installation as best practical.)
- (b) Apply power to system and allow system to operate in accordance with system control functions (actual intended operation).
- (c) Every 15 minutes manually override system controller to demand a system heating load requirement for 15 minutes. (Breadboard heat load shall be adjusted to provide 70°F outlet temperature of load device.
- (d) Every two hours during daytime hours a two minute 6 gpm demand shall be imposed on the hot water subsystem. Every six hours during night hours a 2 minute 6 gpm demand shall be imposed on hot water subsystem.

During system test a one-time test will be conducted on the hot water subsystem that simulates total exhaustion of the hot water tank and a resultant evaluation of the time required to recharge the hot water subsystem preheat tank.

NOTE: As the test progresses the time sequence, duration and parameters of steps (c) and (d) may be adjusted by the test conductor to provide a more appropriate test commensurate with local weather conditions. Any adjustments will be properly noted and recorded.

- (e) Allow system to operate the maximum number of days practical. Duration of testing will be determined by the test conductor with direction from MSFC SIMS contract COR or his designated representative.
- (f) The following data measurements shall be made and recorded during system testing:

<u>Measurement</u>	<u>Parameter</u>
- Solar radiation	Btu/hour/ft. ² vs. time of day
- Ambient temperature	°F vs. time of day
- Wind speed/direction	mph/direction vs. time of day
- Relative humidity	% vs. time of day
- Cloud cover	cloud cover vs. time of day
- Collector inlet temperature	°F vs. time of day in hours
- Collector outlet temperature	°F vs. time of day in hours
- Collector absorber temperature	°F vs. time of day in hours
- Collector delta temperature	°F vs. time of day in hours
- Storage inlet temperature	°F vs. time of day in hours
- Storage outlet temperature	°F vs. time of day in hours
- (3) Internal storage temperature	°F vs. time of day in hours
- System air inlet temperature to load	°F vs. time of day in hours

MeasurementParameter

- System air outlet temperature from load	$^{\circ}\text{F}$ vs. time of day in hours
- Load device inlet temperature	$^{\circ}\text{F}$ vs. time of day in hours
- Load device outlet temperature	$^{\circ}\text{F}$ vs. time of day in hours
- Hot water coil inlet temperature	$^{\circ}\text{F}$ vs. time of day in hours
- Hot water coil outlet temperature	$^{\circ}\text{F}$ vs. time of day in hours
- Hot water preheat tank temperature	$^{\circ}\text{F}$ vs. time of day in hours
- City water supply temp to hot water subsystem	$^{\circ}\text{F}$ vs. time of day in hours
- Hot water system outlet temperature	$^{\circ}\text{F}$ vs. time of day in hours
- System temporary shelter temperature	$^{\circ}\text{F}$ vs. time of day in hours
- Air flow thru collectors	cfm vs. time of day in hours
- Air flow thru storage	cfm vs. time of day in hours
- Air flow thru load	cfm vs. time of day in hours
- Liquid flow thru load device	gpm vs. time of day in hours
- Liquid flow hot water load	gpm vs. time of day in hours
- Collection loop blower power	watts vs. time of day in hours
- System load loop blower power	watts vs. time of day in hours
- System damper motors power	watts vs. time of day in hours
- Hot water subsystem power	watts vs. time of day in hours

- (g) Test data taken from the measurements identified in step (f) shall be provided in plot form.

5.3 System Development Verification Hardware - System development verification analysis will be performed on the total system design. System development verification testing will be conducted on a partially configured system utilizing simulated system energy transport ducting and major subsystems of the prototype system. This method of test evaluation is dictated by the technical aspects of each individual system and the test breadboard facility design. This method is both technically sound and cost effective. Cost effectiveness will result primarily from less hardware handling and no utilization of prototype system auxiliary energy. Auxiliary energy subsystem will be thoroughly evaluated by engineering analysis.

Prototype system development verification testing will be conducted utilizing the following system configured hardware and subsystems:

- Solar collectors (total system complement)
- Air handling device (transport blowers)
- Storage subsystem
- Hot water subsystem
- System controller
- Simulated system ductwork
- Data collection sensors

During system test the above prototype system hardware (excluding solar collectors) shall be housed in a temporary shelter with the shelter ambient temperature maintained between 35° and 100°F. This will prevent the solar system from being exposed to harsh environments and will provide an approximate simulation of the service use environment.

5.4 System Development Verification Test Procedures - Test procedures for conducting prototype system verification testing will be prepared and submitted to MSFC for approval. These procedures will describe the hardware configuration for testing, detailed test methods and procedures, sketches of test setup, test time, limits, data and report

requirements, and all other procedural information pertinent to test evaluation program.

- 5.5 System Design Changes During Development Verification - Any design changes occurring during development verification will be verified by engineering analysis or test evaluation. Ample data will be provided for each design change to verify that the resultant change meets performance criteria requirements and that the resultant change has no adverse effects on the total system performance.
- 5.6 Development Verification Data - Test data accumulated during the early stages of development testing will be thoroughly evaluated and assessments will be performed on necessary system design changes. This will assure early design maturity of prototype system M/N 1.
- 5.7 Development Verification Extent/Level - Development verification program will be conducted to the extent necessary to verify that the final prototype system design meets or exceeds the requirements of the system performance specification and the interim performance criteria or that any requirement which has not been met has been properly dispositioned and MSFC approved by a deviation approval request. Any such deviation from the specified requirements will be documented in the final verification report and will become a part of the prototype system performance specification.
- 5.8 Additional Development Testing - Additional testing and evaluations other than those specified herein may be accomplished. Additional testing and evaluations will be coordinated with MSFC SIMS contracting officer or his designated representative. Additional testing and evaluation will be properly controlled, documented and reported.

6.0 QUALIFICATION VERIFICATION REQUIREMENTS/PROCEDURE

- 6.1 Qualification Verification Requirements - Requirements for qualification verification are as follows:
- Verification that the prototype system meets or exceeds the requirements of system performance specification. These requirements are:

ORIGINAL PAGE IS
OF POOR QUALITY

Interim Performance Criteria Requirements
Government Directed Requirements
System Identification Requirement

Site Identification Requirement
System Heating Capacity Requirement
Auxiliary Energy Requirement
Hot Water Requirement
Operating Requirements
System Physical Requirements (Design Life, Weight,
Dimensions)

6.2 Qualification Verification Procedures - Procedures for verification of each qualification verification requirement are contained in the following subparagraphs.

6.2.1 Interim Performance Criteria Requirement - An analysis will be conducted on prototype system M/N 1 to satisfy this requirement. Each interim performance criteria requirement will be analyzed individually and recorded on an interim performance criteria certification form. This form will indicate compliance or non-compliance to the requirement and will identify the evaluation method utilized to satisfy the requirement. A sample copy of the interim performance criteria certification form is contained in Appendix I of this document. The certification form when completed will become a part of the final verification report.

6.2.2 Government Directed Requirements - This requirement will be satisfied by an analysis of the directed requirement, prototype system and the system performance specification to verify that the directed requirements have been satisfied.

6.2.3 System Identification Requirement - This requirement will be satisfied by review of performance specification and the prototype system to verify that the system is properly identified (type, contractor name, system model no.).

6.2.4 Site Identification Requirement - This requirement will be satisfied by review of performance specification to verify that the site for the prototype system is properly identified and described.

- 6.2.5 System Heating Capacity Requirement - This requirement will be satisfied by an analysis of the prototype system design and the climate conditions anticipated for the selected site at which the prototype system will be located. Test data obtained during system development testing will be utilized to verify the design models for the prototype system.
- 6.2.6 Auxiliary Energy Requirement - This requirement will be satisfied by an analysis of the prototype system load requirements and the prototype system auxiliary energy subsystem design.
- 6.2.7 Hot Water Requirement - This requirement will be satisfied by an analysis of the prototype system design and the hot water load requirements specified for the prototype system. Test data obtained during system development testing will be utilized to verify the design models for the hot water subsystem.
- 6.2.8 Operating Requirements - This requirement will be satisfied by an analysis of the prototype system design and the system operating requirements (maximum power to drive system, average yearly electrical power, water requirements). Test data obtained during system development testing will be utilized to verify the design models for the prototype system.
- 6.2.9 System Physical Requirements - This requirement will be satisfied by an analysis of the prototype system design and the system physical requirements (design life, weight, dimensions).

6.3 Prototype System Qualification

- 6.3.1 Qualification verification will consist of a critical analysis of the prototype system design at the start of development verification versus the system design at completion of development verification. An assessment of all changes implemented during

development verification will be made. All test, analysis, and evaluation data originating prior to and during development verification will be analyzed and evaluated to the requirements of the prototype system performance specification and interim performance criteria.

6.3.2 The prototype system will be considered qualification verified when it is determined that the final system design and hardware has met or exceeded the requirements of the system performance specification and the interim performance criteria or that any requirement which has not been met has been properly dispositioned and MSFC approved by a deviation approval request.

6.3.3 The results of qualification verification will be documented and submitted to MSFC in the prototype system verification report.

7.0 ACCEPTANCE VERIFICATION REQUIREMENTS/PROCEDURE

7.1 Acceptance verification will be conducted on 'prototype system M/N 1 to verify that the system meets all specified requirements. Acceptance verification will consist of the following.

- Inspection of system to verify performance specification and workmanship standards
- Inspection of operational test data and evaluations to verify system performance
- Inspection of acceptance data package
- Inspection of shipping list versus hardware to be delivered
- Inspection of shipping instructions and precautions
- Inspection of documentation required for system (installation, operation, maintenance manuals, system drawings and specifications, etc., in accordance with prototype system performance specification and data package requirements).

- 7.2 The results of acceptance verification will be documented and submitted to MSFC in the prototype system verification report.

8.0 PROTOTYPE SYSTEM VERIFICATION HARDWARE DISPOSITION

Following the completion of prototype system development, qualification and acceptance verification program the system hardware shall be removed from the MSFC test breadboard facility. The system collectors, air handling device, system blowers, hot water subsystem, system controller and data collection sensors shall be prepared for shipment to a designated demonstration site. Shipping instructions shall be in accordance with prototype system M/N 1 shipping instructions.

Simulated duct work, rock storage, test brackets and miscellaneous hardware used during system test will be retained at the MSFC breadboard facility for possible future utilization.

9.0 PROTOTYPE SYSTEM VERIFICATION DOCUMENTATION

- 9.1 Prototype System Test Procedure - Prototype system test procedure for prototype system M/N 1 will be generated utilizing the requirements of this document, prototype system performance specification and drawings. Test procedure will be submitted to MSFC for approval prior to the start of system verification testing. Test procedure shall contain at a minimum the following information.

- (a) Identification of hardware/system to be verified (model No., serial No., mfr., size, description, etc.)
- (b) Test requirements
- (c) Development verification test methods/procedures
- (d) Instrumentation and data requirements
- (e) Location of tests to be conducted

ORIGINAL PAGE IS
OF POOR QUALITY

- (f) Test limits and tolerances
- (g) Test equipment to be utilized
- (h) Detailed test setup and system configuration sketches
- (i) Test reporting procedures

9.2 Verification Report - A final prototype system verification report will be generated following completion of system verification. Final report will be submitted to MSFC and shall contain at a minimum the following:

- (a) Summary - resumé of verification results
- (b) Purpose of verification and requirements to be verified
- (c) Hardware/system identification (model No., serial No., mfr., size, description, etc.)
- (d) Summary of verification procedures
- (e) Results of development verification
- (f) Results of qualification verification
- (g) Results of acceptance verification
- (h) Definition of analysis conducted
- (i) Definition of inspections conducted
- (j) Definition of tests conducted
- (k) Photographs and/or detailed sketches of test setups

(l) Test data (data sheets, charts, graphs, plots, etc.)

(m) Equipment and facilities used for test

(n) Conclusions and recommendations

10.0 VERIFICATION MATRIX

Cross reference matrix for prototype system M/N 1 verification is contained in Appendix II of this document. This matrix is applicable to system selected for physical testing.

ORIGINAL PAGE IS
OF POOR QUALITY

PROTOTYPE SYSTEM MODEL I VERIFICATION

APPROACH/FLOW




FIGURE 1
H-22

APPENDIX I

INTERIM PERFORMANCE CRITERIA
CERTIFICATION FORMS

INTERIM PERFORMANCE CRITERIA
CERTIFICATION

System Type _____

System Model No. _____

System Mfg. _____

Certified by _____
Authorized Representative

Date _____

INTERIM PERFORMANCE CRITERIA CERTIFICATION INSTRUCTIONS

I. Evaluate system for each IPC requirement listed on IPC Certification Sheets. All requirements are to be in accordance with HUD Interim Performance Criteria for Solar Heating and Combined Heating/Cooling Systems and Dwellings. HUD - January 1, 1975.

II. Check each requirement status

Yes - Meets IPC requirement

No - Does not meet IPC requirement

N/A - Requirement not applicable

III. List IPC requirement evaluation method utilized

Analysis

Test

Inspection

Demonstration

Other

IV. All requirements which are not met shall be defined and recorded on IPC Deviation Approval Request (form attached).

IPC REQUIREMENT	IPC NO.	MEETS IPC		N/A	EVALUATION METHOD	COMMENTS
		YES	NO			
Heating and Heating and Cooling System Performance	1.1					
Hot Water System Subsystem Performance	1.2					
Collector Performance	1.3					
Thermal Storage	1.4					
Habitability of Occupied Space	1.5					
Energy Transport Efficiency	1.6					
Control	1.7					
Auxiliary Energy	1.8					

IPC REQUIREMENT	IPC NO.	MEETS IPC		N/A	EVALUATION METHOD	COMMENTS
		YES	NO			
System Design Conditions	2.1					
Mechanical Stresses	2.2					
Leakage Prevention	2.3					
Collector Adjustment	2.4					
Subsystem Isolation	2.5					
Heat Transfer Fluid Quality	2.6					
Piping Supports	2.7					
Excessive Pressure and Temperature Protection	2.8					

IPC REQUIREMENT	IPC NO.	MEETS IPC		N/A	EVALUATION METHOD	COMMENTS
		YES	NO			
Structural Design Basis	3.1					
Failure Loads and Load Capacity	3.2					
Damage Control	3.3					
Cyclic Loads	3.4					
Cutting of Structural Elements	3.5					
Creep and Residual Deflection	3.6					
Hail Resistance	3.7					
Constraint Loads	3.8					
Ponding Conditions	3.9					

ORIGINAL PAGE IS
OF POOR QUALITY

IPC REQUIREMENT	IPC NO.	MEETS IPC		N/A	EVALUATION METHOD	COMMENTS
		YES	NO			
Plumbing and Electrical Installation	4.1					
Fail Safe Controls	4.2					
Fire Safety	4.3					
Toxic and Flammable Fluids	4.4					
Safety	4.5					
Protection of Potable Water and Circulated Air	4.6					
Excessive Surface Temperatures	4.7					
Effects of External Environment	5.1					

IPC REQUIREMENT	IPC NO.	MEETS IPC		N/A	EVALUATION METHOD	COMMENTS
		YES	NO			
Temperature and Pressure Resistance	5.2					
Chemical Compatibility of Components	5.3					
Components Involving Moving Parts	5.4					
Accessibility for Maintenance	6.1					
Installation, Operation and Maintenance Manual	6.2					
Repair and Service Personnel	6.3					
Dwellings/Facility and Site						

IPC REQUIREMENT	IPC NO.	MEETS IPC		N/A	EVALUATION METHOD	COMMENTS
		YES	NO			
Design	7.1					
Adequate Space	7.2					
Functioning of Dwelling/Facility Site	7.3					
Interference with Mechanical Operation	8.1					
Mechanical and Electrical Functioning of Dwelling and Site	8.2					
Mechanical and Electrical Functioning of Connections	8.3					
Structural Integrity	9.1					
Structural Integrity of Dwelling	9.2					
ORIGINAL PAGE IS OF POOR QUALITY.						

IPC REQUIREMENT	IPC NO.	MEETS IPC		N/A	EVALUATION METHOD	COMMENTS
		YES	NO			
Structural Connections	9.3					
Safety of Dwellings and Site	10.1					
Durability	11.1					
Durability and Reliability of Dwelling and Site.	11.2					
Durability and Reliability of Connections	11.3					
Maintainability of H, HC, HW Systems	12.1					
Maintainability of Dwelling and Site	12.2					
Connections	12.3					
Visual Characteristics	13.1					

INTERIM PERFORMANCE CRITERIA DEVIATION APPROVAL REQUEST

1. Report Number	2. Date	3. Prepared By	4. Organization	5. System Type	
6. System Model No.	7. System S/N	8. System Contractor	9. IPC Deviation		
10. IPC Number	11. IPC Paragraph	12. Approved By (IBM)	13. Approved By (MSFC)	14. Date Approved (MSFC)	
15. Description of Deviation					
ORIGINAL PAGE IS OF POOR QUALITY					
16. Probable Cause					
17. Remarks					
18. Deviation Disposition					

APPENDIX II

VERIFICATION CROSS REFERENCE MATRIX

ENGINEERING SPECIFICATION

CODE 20234

ITEM (Name & Part No.)		VERIFICATION CROSS REFERENCE MATRIX		
Prototype System M/N I				
VERIFICATION METHOD:				
1. <u>Similarity</u> 2. <u>Analysis</u> 3. <u>Inspection</u> 4. <u>Test</u> N/N Not Applicable				
PERFORMANCE SPECIFICATION REQUIREMENT	VERIFICATION PHASE			REMARKS
	Development	Qualification	Acceptance	
Interim Performance Criteria	2	2		
Government Directed Requirements	2, 3	2, 3	3	
System Identification Requirements	2, 3	2, 3	3	
Site Identification Requirement			3	
System Heating Requirement	2, 4	2		
Auxiliary Energy Requirement	2, 4	2		
Hot Water Requirement	2, 4	2		
Operating Requirements	2, 4	2		
System Physical Requirements	2	2	3	

ORIGINAL PAGE IS
OF POOR QUALITY

VERIFICATION SUMMARY
FOR
PROTOTYPE SOLAR ENERGY HEATING AND HOT WATER SYSTEM
MODEL NO. 1A

NOVEMBER 19, 1976

PREPARED BY J. G. Daniel

APPROVED BY V. H. Johnson

1.0 PURPOSE

1.1 The purpose of this document is to present a summary of the verification for Prototype Solar Energy Heating and Hot Water System Model No. 1A.

2.0 SCOPE

2.1 This document provides a summary of Prototype System Model No. 1A verification which includes verification of performance specification requirements and acceptance verification requirements. All requirements of the performance specification will be satisfied by analysis.

3.0 VERIFICATION REQUIREMENTS

3.1 Performance Specification Requirements - Prototype System Model No. 1A shall be in accordance with the requirements of Performance Specification (IBM Document No. 7933444). All requirements will be verified by analysis. Requirements are as follows:

- Interim Performance Criteria Requirements

- Government Directed Requirements

- System Identification Requirement

- Site Identification Requirement

- System Heating Capacity Requirement

- Auxiliary Energy Requirement

- Hot Water Requirement

- Operating Requirement

- System Physical Requirements

3.2 Acceptance Verification Requirements - Prototype System Model No. 1A shall be in accordance with the acceptance verification requirements paragraph 7.0 of IBM Document No. 7933445. Requirements are as follows;

- o Inspection of system to verify performance specification and workmanship standards
- o Inspection of acceptance data package
 - Shipping and handling instructions
 - Installation, Operation and Maintenance Manuals
 - Warranty and Test Agency Certification
 - "Final Acceptance" and Shipping Form (DD250) Including forms for all Ship-Separate Items

4.0 VERIFICATION SUMMARY

4.1 Narrative Abstract - Prototype Solar Energy Heating and Hot Water System Model Number 1A was subjected to an analysis verification to verify the requirements of performance specification No. IBM 7933444. Verification was conducted in accordance with the analysis requirements of IBM Document No. 7933445 (Verification Plan/Procedure for Prototype Solar Energy Heating and Hot Water System Model No. 1) . Acceptance verification will be conducted during final acceptance of Prototype System Model No. 1A.

Prototype System Model No. 1A meets all requirements of Performance Specification No. IBM 7933444 with the exception of three (3) interim performance criteria deviations on the system collectors. Deviations are identified in Appendix I of this document.

Verification of prototype system Model 1A will be considered completed with MSFC approval of deviation approval requests for system collectors and with the successful completion of acceptance verification to be conducted during final system acceptance.

4.2 Verification Results

4.2.1 Performance Specification Verification

4.2.1.1 Interim Performance Criteria - Prototype System meets all interim performance criteria requirements with the exception of paragraph 3.2.1 Ultimate Load Combination for Collectors, paragraph 3.3.1 Resistance to Damage for Collectors, and paragraph 5.2.6 Transmission Losses due to Outgassing for Collectors. A deviation from these requirements is requested by IBM since the subject collectors are Government furnished to IBM. Detailed interim performance criteria evaluation is contained in Appendix I of this document.

4.2.1.2 Government Directed Requirements - Requirement has been satisfied by review of performance specification requirements and system design drawings. System 1A meets requirements.

4.2.1.3 System Identification Requirement - Requirement has been satisfied by identification of system in the performance specification (system type, contractor name, system model number). System 1A meets requirements.

4.2.1.4 Site Identification Requirement - Requirement has been satisfied by identifying site location in the performance specification. System 1A meets requirements.

4.2.1.5 System Heating Capacity Requirement - Requirement has been satisfied by analysis of system design. System 1A meets requirements.

4.2.1.6 Auxiliary Energy Requirement - Requirement has been satisfied by analysis of system design. System 1A meets requirements.

4.2.1.7 Hot Water Requirement - Requirement has been satisfied by analysis of system design. System 1A meets requirements.

4.2.1.8 Operating Requirements - Requirement has been satisfied by analysis of system design. System 1A meets requirements.

4.2.1.9 System Physical Requirements - Requirement has been satisfied by analysis of system design. System 1A meets requirements.

4.3 Acceptance Verification Requirements

4.3.1 Inspection of System - This requirement will be satisfied during final acceptance of System Model No. 1A.

4.3.2 Inspection of Acceptance Data Package - This requirement will be satisfied during final acceptance of System Model No. 1A.

5.0 VERIFICATION REPORT

5.1 A final verification report for prototype system Model No. 1A will be prepared and submitted to MSFC thirty days following system acceptance. Report will be prepared in accordance with paragraph 9.2 of IBM Document No. 7933445 except that references to testing and qualification verification will be omitted.

APPENDIX I

PROTOTYPE SYSTEM MODEL NO. 1A
INTERIM PERFORMANCE CRITERIA EVALUATION

INTERIM PERFORMANCE CRITERIA
CERTIFICATION

System Type Heating & Hot Water (Air System)

System Model No. Prototype M/N 1A

System Mfg. IBM

Analysis Conducted by J. G. Daniel

Date NOVEMBER 18, 1976

INTERIM PERFORMANCE CRITERIA CERTIFICATION INSTRUCTIONS

I. Evaluate system for each IPC requirement listed on IPC Certification Sheets. All requirements are to be in accordance with HUD Interim Performance Criteria for Solar Heating and Combined Heating/Cooling Systems and Dwellings. HUD - January 1, 1975.

II. Check each requirement status

Yes - Meets IPC requirement

No - Does not meet IPC requirement

N/A - Requirement not applicable

III. List IPC requirement evaluation method utilized.

Analysis

Test

Inspection

Demonstration

Other

IV. All requirements which are not met shall be defined and recorded on IPC Deviation Approval Request (form attached).

ORIGINAL PAGE IS
OF POOR QUALITY

IPC REQUIREMENT	IPC NO.	MEETS IPC		N/A	EVALUATION METHOD	COMMENTS
		YES	NO			
Heating and Heating and Cooling System Performance	1.1	X			Analysis	Cooling Portion N/A
Hot Water System Subsystem Performance	1.2	X			Analysis	
Collector Performance	1.3	X			Analysis	
Thermal Storage	1.4	X			Analysis	
Habitability of Occupied Space	1.5	X			Analysis	
Energy Transport Efficiency	1.6	X			Analysis	
Control	1.7	X			Analysis	
Auxiliary Energy	1.8	X			Analysis	

IPC REQUIREMENT	IPC NO.	MEETS IPC		N/A	EVALUATION METHOD	COMMENTS
		YES	NO			
System Design Conditions	2.1	X			Analysis	
Mechanical Stresses	2.2	X			Analysis	
Leakage Prevention	2.3	X			Analysis	Applicable portions of system will be pressure tested during system installation
Collector Adjustment	2.4	X			Analysis	
Subsystem Isolation	2.5	X			Analysis	
Heat Transfer Fluid Quality	2.6	X			Analysis	
Piping Supports	2.7	X			Analysis	
Excessive Pressure and Temperature Protection	2.8	X			Analysis	
ORIGINAL PAGE IS OF POOR QUALITY						

IPC REQUIREMENT	IPC NO.	MEETS IPC		N/A	EVALUATION METHOD	COMMENTS
		YES	NO			
Structural Design Basic	3.1	X				
Failure Loads and Load Capacity	3.2					
Ultimate Load Combination	3.2.1		X			No data available to substantiate collector meets requirements
Damage Control	3.3					
Resistance to Damage	3.3.1		X			No data available to substantiate collector meets requirements
Cyclic Loads	3.4					
Cutting of Structural Elements	3.5	X			Analysis	
Creep and Residual Deflection	3.6	X			Analysis	
Half Resistance	3.7	X			Analysis	
Constraint Loads	3.8					
Ponding Conditions	3.9	X			Analysis	

IPC REQUIREMENT	IPC NO.	MEETS IPC		N/A	EVALUATION METHOD	COMMENTS
		YES	NO			
Plumbing and Electrical Installation	4.1	X			Analysis	
Fail Safe Controls	4.2	X			Analysis	
Fire Safety	4.3	X			Analysis	
Toxic and Flammable Fluids	4.4	X			Analysis	
Safety	4.5	X			Analysis	
Protection of Potable Water and Circulated Air	4.6	X			Analysis	
Excessive Surface Temperatures	4.7	X			Analysis	
Effects of External Environment	5.1	X			Analysis	
ORIGINAL PAGE IS OF POOR QUALITY						

IPC REQUIREMENT	IPC NO.	MEETS IPC		N/A	EVALUATION METHOD	COMMENTS
		YES	NO			
Temperature and Pressure Resistance	5.2	X			Analysis	
Transmission losses due to outgassing	5.2.6		X			No data available to substantiate collector meets requirements
Chemical Compatibility of Components	5.3	X			Analysis	
Components Involving Moving Parts	5.4	X			Analysis	
Accessibility for Maintenance	6.1	X			Analysis	
Installation, Operation and Maintenance Manual	6.2	X			Analysis	
Repair and Service Personnel	6.3	X			Analysis	
Dwellings/Facility and Site						

IPC REQUIREMENT	IPC NO.	MEETS IPC		N/A	EVALUATION METHOD	COMMENTS
		YES	NO			
Design	7.1	X			Analysis	
Adequate Space	7.2	X			Analysis	
Functioning of Dwelling/Facility Site	7.3	X			Analysis	
Interference with Mechanical Operation	8.1	X			Analysis	
Mechanical and Electrical Functioning of Dwelling and Site	8.2	X			Analysis	
Mechanical and Electrical Functioning of Connections	8.3	X			Analysis	
Structural Integrity	9.1	X			Analysis	
Structural Integrity of Dwelling	9.2	X			Analysis	

IPC REQUIREMENT	IPC NO.	MEETS IPC		N/A	EVALUATION METHOD	COMMENTS
		YES	NO			
Structural Connections	9.3	X			Analysis	
Safety of Dwellings and Site	10.1	X			Analysis	
Durability	11.1	X			Analysis	
Durability and Reliability of Dwelling and Site	11.2	X			Analysis	
Durability and Reliability of Connections	11.3	X			Analysis	
Maintainability of H, HC, HW Systems	12.1	X			Analysis	
Maintainability of Dwelling and Site	12.2	X			Analysis	
Connections	12.3	X			Analysis	
Visual Characteristics	13.1	X			Analysis	

ORIGINAL PAGE IS
OF POOR QUALITY

INTERIM PERFORMANCE CRITERIA DEVIATION APPROVAL REQUEST

1. Report Number 1A-001	2. Date 11-15-76	3. Prepared By T. G. Daniel	4. Organization IBM Dept. K42	5. System Type Heating and Hot Water (AIR)
6. System Model No. 1A	7. System S/N -	8. System Contractor IBM	9. IPC Deviation Ultimate Load Combination (Collectors)	
10. IPC Number HUD Jan. 1, 1975	11. IPC Paragraph 3.2.1	12. Approved By (IBM)	13. Approved By (MSFC)	14. Data Approved (MSFC)

15. Description of Deviation

No data available to substantiate that collectors meet requirements of ultimate load combinations.

16. Probable Cause

17. Remarks

- Load testing of collectors will be accomplished at MSFC.
- Data received from testing will verify collector ability to meet/not meet IPC requirements for ultimate load combinations.

18. Deviation Disposition

System deviation is requested for collectors.
Collectors are Government furnished to IBM.

INTERIM PERFORMANCE CRITERIA DEVIATION APPROVAL REQUEST

1. Report Number IA-002	2. Date 11-16-76	3. Prepared By T. G. Daniel	4. Organization IBM Dept. K42	5. System Type Heating and Hot Water (Air)	
6. System Model No. IA	7. System S/N -	8. System Contractor IBM	9. IPC Deviation Resistance to Damage		
10. IPC Number IRJD Jan. 1, 1975	11. IPC Paragraph 3.3.1	12. Approved By (IBM)	13. Approved By (MSFC)	14. Date Approved (MSFC)	
15. Description of Deviation No data available to substantiate that collectors meet requirements of resistance to damage.					
16. Probable Cause					
17. Remarks - Load testing of collectors will be accomplished at MSFC. - Data received from testing will verify collector ability to meet/not meet IPC resistance to damage requirements.					
18. Deviation Disposition - System deviation is requested for collectors. - Collectors are Government furnished to IBM.					

ORIGINAL PAGE IS
OF POOR QUALITY

INTERIM PERFORMANCE CRITERIA DEVIATION APPROVAL REQUEST

FORM 1

1. Report Number 1A-003	2. Date 11-16-76	3. Prepared By T. G. Daniel	4. Organization IBM Dept. K42	5. System Type Heating and Hot Water (Air)
6. System Model No. 1A	7. System S/N -	8. System Contractor IBM	9. IPC Deviation Transmission losses due to outgassing	
10. IPC Number IHUJ Jan. L, 1975	11. IPC Paragraph 5.2.6	12. Approved By (IBM)	13. Approved By (MSFC)	14. Date Approved (MSFC)

15. Description of Deviation

No data available to substantiate that collectors meet requirements of transmission losses due to outgassing.

16. Probable Cause

17. Remarks

- Weathering test will be conducted on collectors at MSFC.
- Data received from testing will verify collector ability to meet/not meet IPC requirements for outgassing.

18. Deviation Disposition

- System deviation requested for collectors.
- Collectors are Government furnished to IBM.

APPENDIX II

PROTOTYPE SYSTEM MODEL NO. 1A

SYSTEM 1 PERFORMANCE ANALYSIS SUMMARY

ORIGINAL PAGE IS
OF POOR QUALITY

SYSTEM I PERFORMANCE ANALYSIS SUMMARY

Evaluation of the System I design was accomplished using a detailed simulation model of the system formulated using TRNSYS-A Transient Simulation Program for Solar Energy Systems. The purpose of this report is to summarize the predicted system performance and the methods used to achieve it.

Each major component of the System I design was modeled in detail resulting in time dependent interaction between the subsystems and producing true system-level performance predictions. The simulation period was one year in duration at integrating time steps of one-fourth hour.

Inputs to the simulation in addition to system configuration and subsystem performance were forcing functions of hourly weather and space heating and hot water load information. Outputs are extensive and include system and subsystem performance such as system temperatures, collector performance, loads, and percent contribution of the solar energy system.

Sensitivity studies were conducted to determine optimum values for several key system parameters:

- o System flowrate was varied from 900 to 3000 CFM (1.5 to 5 CFM per square foot of collector). Based on the results, a value of 1500 CFM ($2.5 \text{ CFM/FT}^2\text{c}$) was chosen.
- o The effect of the size of the storage subsystem was evaluated over the range of 150 to 600 FT^3 of pebble bed (5 to 20 $\text{BTU/}^\circ\text{F/FT}^2\text{c}$). Results showed that improvement in performance was significant enough to offset additional costs up to 600 FT^3 ; and the selection of a specific value should be limited only by architectural constraints on the building design. A storage volume of 500 FT^3 ($17.9 \text{ BTU/}^\circ\text{F/FT}^2\text{c}$) was thus selected.

ORIGINAL PAGE IS
OF POOR QUALITY

- o The temperature differential setting controlling collector operation was varied from 25 to 45 F degrees to identify the value giving optimum long term system performance. The resultant value was 30 F degrees.

The optimum values determined from these parametric studies were incorporated into the system design.

The following paragraphs define in somewhat more detail the pertinent parameters and conditions on which the system simulation was based. Finally, the resultant system performance predictions are summarized for the System I design on a monthly and/or yearly basis.

System Configuration

The system simulation schematic is shown in Figure 1. Major components and their defining parameters are listed below.

- o Collector
 - Solar Energy Products manufacturer
 - 591 FT² effective area
 - 45° tilt angle
 - 0° azimuth (due south)
 - Hottel-Whillier-Bliss Model
 - SEPCO performance data
- o Storage
 - 500 FT³ bed volume
 - 7.2'W x 10.8'L x 6.5'H
 - 17.9 BTU/°F/FT²c
 - 3/4 - 2 1/2" pebble size
 - R11 Insulation
 - 10 layer model
 - Inside building




Figure 1 SYSTEM SIMULATION SCHEMATIC (TRNSYS)

- o DHW Heat Exchanger
 - Cross flow
 - 725 BTU/HR^oF UA
 - 4 GPM water flowrate
- o DHW Pump
 - 4 GPM
- o DHW Pre-Heat Tank
 - 80 gallons
 - Un-stratified
 - R-22 insulation
- o DHW Tank
 - 52 gallons
 - Electrical auxiliary
 - 140^oF thermostat
 - Unstratified
 - R-22 insulation
 - 55^oF make-up water temperature
- o Air Handler.
 - 1500 CFM
- o Heat-Pump (Air-to-Air)
 - Westinghouse Model HP036D
 - Vendor performance data

- o Auxiliary Heater

- Electric resistance
- 16.7 KW capacity

- o Thermostat

- First stage heating at room temperature below 68°F
- Second stage heating at room temperature below 66°F
- Air conditioning at room temperature above 77°F

- o Controls

- Numerous controllers are used in the simulation to accomplish the required operation. The functional control modes are described below.
- Collector on (fan turned on) when collector surface temperature exceeds temperature at bottom of storage by 30 F degrees. Collector off (fan off) when collector outlet temperature drops to less than 15 F degrees above bottom of storage. In the summer by-pass mode, the fan operates only when this logic is satisfied and the DHW preheat tank needs heat.
- DHW pump is turned on whenever the collector is operating and the collector outlet temperature exceeds 9F degrees above preheat tank temperature.
- The summer bypass mode is initiated at inception of cooling load requirement; disengaged when heating load begins in Fall.
- When can collect and first stage of room thermostat is satisfied ($T_{ROOM} \geq 68^{\circ}F$ - no requirement for heating) air from collectors is supplied to storage.

- When can collect and have demand for first stage heat, air from collectors is diverted to load. If in this mode load then demands second stage heat ($T_{\text{ROOM}} \leq 66^{\circ}\text{F}$), auxiliary electric strip heater is powered on to supplement.
- When cannot collect and have demand for first stage heat and temperature in top of storage is $\geq 90^{\circ}\text{F}$, heat is supplied from the pebble bed to the load. If in this mode load then demands second stage heat ($T_{\text{ROOM}} \leq 66^{\circ}\text{F}$), auxiliary electric strip heater is powered on to supplement.
- When cannot collect and have demand for first stage heat and temperature in top of storage is $< 90^{\circ}\text{F}$, the heat pump is powered up. If in this mode load then demands second stage heat ($T_{\text{ROOM}} \leq 66^{\circ}\text{F}$), auxiliary electric strip heater is powered on to supplement.

Weather Data

Measured hourly weather data, obtained from the U.S. Weather Bureau, was used as input to the simulation program. This provided a means of analyzing the performance of the system for realistic climatological conditions. Since hourly weather data are not available for Huntsville, data for Nashville for the year 1957 was selected for use as the design year. This year was selected because it approximated the typical winter conditions experienced in Huntsville, Alabama.

Inputs to the program from the weather tapes are hourly values of total insolation on a horizontal surface and the ambient temperature. A solar radiation processor component within the simulation model converts the horizontal insolation values to the proper value incident on the tilted collector surface. The ambient temperature is used in conjunction with the building conductance (UA) and the inside room temperature to actively determine the heat loss rate. For information only, the average daily insolation for each month and a computed value of the heating degree ($^{\circ}\text{F}$) days per month are provided in Table I.

Table I. Summary of Weather Data		
Month	Insolation on Horizontal Surface (BTU/FT ²) - Avg daily	Heating Degree Days (°F)
January	597	847
February	834	506
March	1136	530
April	1635	188
May	1833	67
June	1882	3
July	2176	1
August	2071	8
September	1360	35
October	1136	305
November	821	492
December	702	612

ORIGINAL PAGE IS
OF POOR QUALITY

Heating and Hot Water Loads

The space heating and service hot water loads are handled independently in the system model. The space heating load is modeled as a single node with a thermal capacitance of 2.1×10^4 BTU/ $^{\circ}$ F and a heat loss rate (UA) of 750 BTU/Hour- $^{\circ}$ F. The internal temperature was maintained during the heating season with a two stage thermostat. The thermostat settings were 68 $^{\circ}$ F and 66 $^{\circ}$ F for the first and second stages respectively. The hourly heating load of the building (Q_L) is expressed in the following equation:

$$Q_L = UA (T_R - T_{amb})$$

where $UA = 750$ BTU/Hour - $^{\circ}$ F

$$T_R = \text{Inside temperature } (^{\circ}\text{F})$$

$$T_{amb} = \text{Ambient temperature } (^{\circ}\text{F})$$

The hot water load is established by a daily usage schedule. This schedule is defined on a hourly basis with the outlet water at 140 $^{\circ}$ F and the inlet at 55 $^{\circ}$ F. A total of 41.5 gallons per day was established for this particular site. For a residential application, this would typically be doubled. The following table presents the daily usage schedule on an hourly basis:

Table II. Daily Hot Water Consumption

Hour of Day	Gallons/Hour
0-7	0
7-8	2.5
8-9	5
9-10	2.5
10-11	12.5
11-12	0
12-13	2.5
13-14	0
14-16	1
16-18	0
18-20	2.5
20-21	7.5
21-23	1
23-24	0

A listing of the input data for the TRNSYS System I model is shown in Table III.

Performance Results

The results of the one-year simulation are presented graphically in Figure 2 through 4 for each month. As shown:

- o The annual contribution of the solar energy system to the space heating load is 58%.
- o The annual contribution of the solar energy system to the domestic hot water load is 57%.
- o The annual contribution of the solar energy system to the overall load is 58%.

It should be noted that these results are highly dependent on a number of assumed input conditions, including weather. Although the conditions used for this simulation are typical, significant variations can occur.

ORIGINAL PAGE IS
OF POOR QUALITY

SPACE HEATING




FIGURE 2

HOT WATER




FIGURE 3

ANNUAL SYSTEM PERFORMANCE




FIGURE 4

ORIGINAL PAGE IS
OF POOR QUALITY

TPNSYS - A TRANSIENT SIMULATION PROGRAM
 FROM THE SOLAR ENERGY LAB THE UNIVERSITY OF WISCONSIN
 VERSION 5 6/1/76

SIMULATION 0.0 7.2007 02 2.5007-01
 WIDTH 72

MAP

LIMITS 25 20

TOLERANCES -2.000E-01 -2.000E-01

SYSTEM 1A PERFORMANCE SENSITIVITY STUDY

PARAMETER	VALUE			
A. COLLECTOR CONTROL DELTA T	25	35	45	FEES
B. STORAGE CAPACITY	5	10	15	BTU/F/FT2
C. FLOWRATE	1.5	2	2.5	CFM/FT2

RUN NUMBER 25

A B C
 30F 17.9 2.5

UNIT 9 TYPE 9 CARD READER
 PARAMETERS 6
 9.000E 00 1.000E 00 5.000E 00 5.556E-01 -2.730E 02
 8.000E 00 1.135E 01 0.0

UNIT 16 TYPE 16 RADIATION PROCESSOR
 PARAMETERS 7
 1.000E 00 1.000E 00 3.600E 01 4.500E 01 0.0
 4.870E 03 2.000E-01
 INPUTS 1
 9, 8
 0.0

UNIT 1 TYPE 1 AIR COLLECTOR (MODE 1)
 PARAMETERS 7
 1.000E 00 5.500E 01 9.000E-01 1.012E 00 9.200E-01
 2.860E 01 8.500E-01
 INPUTS 4
 42, 1 42, 2 9, 5 16, 1

ORIGINAL PAGE IS
 OF POOR QUALITY

2.000E 01 0.0 0.0 0.0

UNIT 2 TYPE 2 COLLECTOR CONTROLLER

PARAMETERS 3
 3.000E 00 1.670E 01 3.300E 00
 INPUTS 3
 1, 1 10, 1 2, 1
 2.000E 01 2.000E 01 0.0

UNIT 11 TYPE 11 DAMPER NO. 1

PARAMETERS 1
 3.000E 00
 INPUTS 5
 10, 3 10, 4 43, 1 43, 2 2, 1
 3.300E 01 0.0 3.300E 01 0.0 0.0

UNIT 43 TYPE 5 DHW HEAT EXCHANGER

PARAMETERS 4
 3.000E 00 1.378E 03 1.012E 00 4.190E 00
 INPUTS 4
 1, 1 1, 2 44, 1 44, 2
 2.500E 01 0.0 2.500E 01 0.0

UNIT 5 TYPE 21 DHW PUMP CONTROLLER (AND/OR)

PARAMETERS 2
 1.000E 00
 INPUTS 8
 1, 1 45, 3 0, 0 0, 0 45, 3
 0, 0 0, 0 0, 0
 2.500E 01 2.500E 01 -5.000E 00 0.0 2.500E 01
 1.000E 03 1.000E 00 3.200E 01

UNIT 44 TYPE 3 DHW PUMP

PARAMETERS 1
 9.040E 02
 INPUTS 3
 45, 1 45, 2 36, 1
 2.500E 01 0.0 0.0

UNIT 45 TYPE 4 TANK1 (PRE-HEAT)

PARAMETERS 5
 3.000E 01 1.730E 00 4.190E 00 1.000E 03 3.250E 00
 INPUTS 5
 43, 3 43, 4 0, 0 47, 1 12, 4
 2.500E 01 0.0 1.280E 01 0.0 2.500E 01
 DERIVATIVES 1
 3.500E 01

UNIT 7 TYPE 13 RELIEF VALVE, HOT WATER DELIVERY TEMP CONTR

PARAMETERS 2
 6.000E 01 4.190E 00
 INPUTS 3
 46, 3 46, 4 46, 3
 2.500E 01 0.0 2.500E 01

UNIT 6 TYPE 15 AL DP HW EXCESS HEAT RETURN

PARAMETERS 9
 0.0 0.0 0.0 0.0 1.000E 00
 0.0 2.000E 00 2.000E 00 3.000E 00
 INPUTS 5
 45, 3 7, 3 7, 2 0, 0 0, 0

TABLE III (CONT)

2.500E 01 0.0 0. 4.190E 30 1.000E-03

UNIT 46 TYPE 4 TANK 2 (HW)

PARAMETERS 9

2.000E 01 1.220E 00 4.500E 00 1.000E 03 3.250E 00

1.620E 04 1.000E 00 1.000E 00 6.000E 01

INPUTS 6

0, 0 0, 0 0, 1 45, 4 12, 4

0, 0 0.0 2.500E 01 0.0 2.500E 01

1.000E 00

DERIVATIVES 1

6.000E 01

UNIT 47 TYPE 14 HOT WATER - USE PROFILE (GAL/DAY)

PARAMETERS 56

0.0 0.0 7.000E 00 0.0 7.000E 00

9.420E 00 3.000E 00 9.420E 00 8.000E 00 1.390E 01

9.000E 00 1.390E 01 9.000E 00 9.420E 00 1.000E 01

9.420E 00 1.000E 01 4.710E 01 1.100E 01 4.710E 01

1.100E 01 0.0 1.200E 01 0.0 1.200E 01

9.420E 00 1.300E 01 9.420E 00 1.300E 01 0.0

1.400E 01 0.0 1.400E 01 3.700E 00 1.600E 01

3.700E 00 1.600E 01 0.0 1.800E 01 0.0

1.800E 01 9.420E 00 2.000E 01 1.800E 01 2.000E 01

2.830E 01 2.100E 01 2.830E 01 2.100E 01 3.700E 00

2.300E 01 3.700E 00 2.300E 01 0.0 2.400E 01

0.0

UNIT 30 TYPE 15 HOT WATER SUPPLIED CALCULATOR

PARAMETERS 7

0.0 0.0 0.0 0.0 4.000E 00

1.000E 00 1.000E 00 0.0 0.0 0.0

INPUTS 4

47, 1 0, 0 7, 1 0, 0

0.0 4.190E 00 6.000E 01 1.280E 01

UNIT 37 TYPE 15 CALCULATE QHWSOL

PARAMETERS 3

0.0 0.0 4.000E 00

INPUTS 2

24, 1 24, 2

0.0 0.0

UNIT 14 TYPE 15 FAN CONTROLLER

PARAMETERS 13

-1.000E 00 1.000E 00 0.0 4.000E 00 -1.000E 00

-1.000E 00 0.0 4.000E 00 1.000E 00 7.000E 00

-1.000E 00 1.000E 00 3.000E 00

INPUTS 2

2, 1 31, 1

0.0 0.0

UNIT 17 TYPE 15 FAN CONTROLLER INHIBIT LOGIC #1

PARAMETERS 5

0.0 0.0 0.0 4.000E 00 1.000E 00

INPUTS 3

14, 1 0, 0 40, 1

0.0 1.000E 00 0.0

UNIT 18 TYPE 15 FAN CONTROLLER INHIBIT LOGIC #2

ORIGINAL PAGE IS
OF POOR QUALITY

PARAMETERS 3
 0.0 0.0 1.0 00 00
 INPUTS 2
 5, 1 40, 1
 0.0 0.0

UNIT 40 TYPE 15 FAN CONTROLLER INHIBIT LOGIC #3
 PARAMETERS 3
 0.0 0.0 3.000E 00
 INPUTS 2
 17, 1 18, 1
 0.0 0.0

UNIT 3 TYPE 3 MAIN FAN *****
 PARAMETERS 1
 2.779E 03
 INPUTS 3
 11, 1 11, 2 14, 1
 3.300E 01 0.0 0.0

UNIT 31 TYPE 15 DAMPER NO.2 CONTROLLER *****
 PARAMETERS 4
 0.0 -1.000E 00 2.779E 03 2.000E 00
 INPUTS 1
 20, 2
 0.0

UNIT 21 TYPE 11 DAMPER NO. 2
 PARAMETERS 1
 2.000E 00
 INPUTS 3
 3, 1 3, 2 31, 1
 3.300E 01 0.0 0.0

UNIT 40 TYPE 2 SUMMER BY-PASS CONTROLLER
 PARAMETERS 3
 4.000E 00 5.000E 00 0.0
 INPUTS 3
 12, 4 0, 0 40, 1
 2.000E 01 2.000E 01 0.0

UNIT 41 TYPE 11 BY-PASS DIVERter
 PARAMETERS 1
 2.000E 00
 INPUTS 3
 21, 1 21, 2 40, 1
 2.500E 01 0.0 0.0

UNIT 4 TYPE 15 ATTIC TEMPERATURE
 PARAMETERS 7
 0.0 0.0 1.000E 00 0.0 0.0
 1.000E 00 3.000E 00
 INPUTS 4
 7, 5 0, 0 1, 1 0, 0
 2.500E 01 8.500E-01 2.500E 01 1.500E-01

UNIT 42 TYPE 11 BY-PASS TEE
 PARAMETERS 1
 1.000E 00
 INPUTS 4
 22, 1 22, 2 41, 3 41, 4

TABLE III (CONT)

2.500E 01 0.0 2.5 0E 01 0.0

UNIT 10 TYPE 10 ROCK BED *****
 PARAMETERS 3
 1.012E 00 1.930E 00 7.1 0E 00 1.096E 01 8.200E-01
 1.630E 03 1.630E 00 4.1 0E-01
 INPUTS 5
 41, 1 41, 2 23, 1 23, 2 12, 4
 2.000E 01 0.0 2.000E 01 0.0 2.000E 01
 DERIVATIVES 10
 4.000E 01 3.700E 01 3.500E 01 3.300E 01 3.100E 01
 2.900E 01 2.700E 01 2.500E 01 2.300E 01 2.000E 01

UNIT 22 TYPE 11 TREE-PIECE
 PARAMETERS 1
 1.000E 00
 INPUTS 4
 10, 1 10, 2 23, 3 23, 4
 2.000E 01 0.0 2.000E 01 0.0

UNIT 32 TYPE 15 AL OP, QU POSITIVE ONLY
 PARAMETERS 2
 0.0 8.000E 00
 INPUTS 1
 1, 3
 0.0

UNIT 33 TYPE 15 LOAD CALCULATOR 1750 BTU/HOUR-F
 PARAMETERS 6
 0.0 0.0 4.000E 00 -1.000E 00 1.425E 03
 1.000E 00
 INPUTS 2
 9, 5 12, 4
 2.000E 01 0.0

UNIT 34 TYPE 15 COOLING LOAD
 PARAMETERS 2
 0.0 8.000E 00
 INPUTS 1
 33, 1
 0.0

UNIT 35 TYPE 15 HEATING LOAD
 PARAMETERS 3
 0.0 7.000E 00 8.000E 00
 INPUTS 1
 33, 1
 0.0

UNIT 38 TYPE 15
 PARAMETERS 3
 0.0 0.0 3.000E 00
 INPUTS 2
 33, 1 10, 7
 0.0 0.0

UNIT 39 TYPE 15
 PARAMETERS 1
 3.000E 00
 INPUTS 2
 8, 1 8, 3

ORIGINAL PAGE IS
 OF POOR QUALITY

TABLE "A" (CONT)

0.0 0.0

UNIT 20 TYPE 20 AIR TO AIR HEAT PUMP

PARAMETERS 17
 1.012E 00 2.779E 03 2.0 0E 01 2.500E 01 1.000E 03
 1.000E 01 1.000E 01 5.0 0E 00 7.000E 00 5.000E 00
 2.200E 01 2.223E 03 1.000E 00 3.200E 01 1.000E 00
 2.100E 01 0.0
 INPUTS 6
 3, 1 21, 4 9, 5 38, 1 39, 1
 12, 4
 2.000E 01 0.0 0.0 0.0 0.0
 0.0

UNIT 23 TYPE 11 VIRTUAL DAMPER

PARAMETERS 1
 2.000E 00
 INPUTS 3
 20, 1 20, 2 2, 1
 2.000E 01 0.0 0.0

UNIT 15 TYPE 15 HEAT ADDER

PARAMETERS 13
 0.0 0.0 0.0 0.0 0.0
 0.0 0.0 4.000E 00 3.000E 00 3.000E 00
 3.000E 00 3.000E 00 3.000E 00
 INPUTS 7
 33, 1 29, 1 20, 15 20, 9 20, 5
 10, 7 20, 12
 0.0 0.0 0.0 0.0 0.0
 0.0 0.0

UNIT 12 TYPE 12 ONE-WIDE HOUSE

PARAMETERS 9
 4.000E 00 0.0 4.000E 04 0.0 1.000E 00
 1.000E 00 1.000E 00 0.0
 INPUTS 4
 0, 0 0, 0 9, 5 15, 1
 0.0 0.0 0.0 0.0
 DERIVATIVES 1
 2.000E 01

UNIT 8 TYPE 8 THREE STAGE ROOM THERMOSTAT

PARAMETERS 6
 5.000E 00 1.000E 00 0.0 2.500E 01 2.000E 01
 1.900E 01
 INPUTS 2
 12, 4 0, 0
 2.000E 01 1.000E 02

UNIT 29 TYPE 15 AUX FURNACE

PARAMETERS 1
 1.000E 00
 INPUTS 2
 8, 2 0, 0
 0.0 6.000E 04

UNIT 36 TYPE 15 PUMP TIME AND FUNCTION

PARAMETERS 3
 0.0 0.0 1.000E 00
 INPUTS 2

TABLE III CONT

46, 1 0.0	5, 0.0				
UNIT 24	TYPE 24	INTEGRATOR 1			
PARAMETERS 1					
7.200E 02					
INPUTS 10					
30, 1	46, 5	37, 1	20, 5	29, 1	
20, 15	30, 1	16, 1	30, 1	10, 1	
0.0	0.0	0.0	0.0	0.0	
0.0	0.0	0.0	0.0	0.0	
UNIT 19	TYPE 24	INTEGRATOR 2			
PARAMETERS 1					
7.200E 02					
INPUTS 7					
36, 1	10, 2	10, 4	31, 1	10, 6	
20, 12	20, 14				
0.0	0.0	0.0	0.0	0.0	
0.0	0.0				
UNIT 50	TYPE 24	INTEGRATOR 3			
PARAMETERS 1					
7.200E 02					
INPUTS 5					
16, 2	16, 3	16, 4	16, 5	16, 6	
0.0	0.0	0.0	0.0	0.0	
UNIT 27	TYPE 25	PRINTER 3			
PARAMETERS 1					
7.200E 02					
INPUTS 5					
50, 2	50, 3	50, 4	50, 5		
HBTILT	HOTILT	HTHORZ	HBHORZ	HCHORZ	
UNIT 25	TYPE 25	PRINTER 1			
PARAMETERS 1					
7.200E 02					
INPUTS 10					
24, 1	24, 2	37, 1	24, 4	24, 5	
24, 6	24, 7	24, 8	24, 9	24, 10	
QHSUP	QAUXHW	QHSOL	QDH	QAUXH	
OR2	QU	HTILT	WAH	FANTIM	
UNIT 26	TYPE 25	PRINTER 2			
PARAMETERS 1					
7.200E 02					
INPUTS 7					
19, 1	19, 2	19, 3	19, 4	19, 5	
19, 6	19, 7				
PUNTIM	COLSTO	STOLOD	SOLLOD	OBED	
QAC	WAC				
UNIT 13	TYPE 26	PLOTTER			
PARAMETERS 4					
7.200E 02	0.0	8.640E 03	1.000E 00		
INPUTS 5					
27, 1	24, 1	24, 4	24, 5	24, 6	
QHSOL	QHSUP	QDH	QAUXH	OR2	

END

ORIGINAL PAGE IS
OF POOR QUALITY

PROTOTYPE SYSTEM 1
HAZARDS ANALYSIS

November 1976

ORIGINAL PAGE IS
OF POOR QUALITY

PROTOTYPE SYSTEM NO. 1
HAZARDS ANALYSIS

A hazards analysis was performed to define potential hazards or undesired events relative to the System No. 1 design, to identify the safety requirement to eliminate the hazard, and to indicate the means of compliance with each safety requirement. A summary of the hazards analysis results are given in Table 1.

All potential hazards identified are minor level hazards and no major hazard levels have been found. No residual hazards have been identified, and no failure modes have been identified which would contribute to the occurrence of a hazard. As shown in Table 1, the use of standard off-the-shelf hardware minimizes potential hazards.

HAZARD DATA SUMMARY

Areas of Consideration	Safety Requirement	Hazard/Undesired Event	Means of Compliance
Mechanical Protection 5-8 ORIGINAL PAGE IS OF POOR QUALITY	• Mechanical Hazards not significantly greater than conventional residence.	• Injury due to pinch or sharp edges. • Short circuits due to wire abrasion. • Mechanical damage due to faulty installation. • Mechanical damage due to migration of components during operation • Rotating Equipment • Humidity and Fungus	• All operator and service area edges rounded. • Design does not present unusual or unique mechanical hazards. • Approved tie down, strain relief and feed through hardware and installation. • Drawings provided with sufficient design detail and notes to highlight proper installation. • Motor, Belt and Fan enclosed • DHW Pump has all rotating parts enclosed. • All equipment mounted within the residence.

HAZARD DATA SUMMARY

Areas of Consideration	Safety Requirement	Hazard/Undesired Event	Means of Compliance
J-4 Primary Voltages	• Section 516 and 616 MPS (4900.1 and 4910.1). • Part E of ANSI A119.1 • Hazard exposure not significantly greater than conventional residence.	• Personnel Shock • Equipment damage due to short circuit or over-load.	• Use conventional equipment and installation. • All external metal parts, surfaces and shields to be at electrical ground. • UL approved 15A circuit breaker • All wire UL approved • Primary voltage in service areas are protected by shields or shrink sleeve insulation. • Stored energy minimal • Low voltage control circuit
Secondary Voltages		• Stored Energy • Short between primary and secondary circuits	• Transformer isolation and physical separation between primary and secondary circuits.
Electromagnetic Interference	• Maintain circuit separation	• Interference between power, data and control functions	• Sensor and control wires separated. Sensor inputs are protected by ground wires for each channel.

HAZARD DATA SUMMARY

Areas of Consideration	Safety Requirement	Hazard/Undesired Event	Means of Compliance
Fire Safety J-5	• Use materials which do not present a fire hazard significantly greater than conventional systems • Proper clearance and venting of elevated temperature surface • Emergency egress and access not be less than conventional system • Identified and accessible main shut-off valves and switches	• Flammability of materials • Air flow loss due to fan failure or blockage • Occupant entrapment • Difficulty in terminating system operation or isolating failure	• Used conventional components of proven safety • UL recognized components as • UL acceptance of air handler and control subsystems • Interlocks to insure fan operation when heat strips in use • Conventional design criteria met for egress and access. Convenient and accessible equipment room • Main shutoff valves and switches are clearly labeled and easily accessible within equipment room

ORIGINAL PAGE IS
OF POOR QUALITY

HAZARD DATA SUMMARY

Areas of Consideration	Safety Requirement	Hazard/Undesired Event	Means of Compliance
Domestic Hot Water	- Where applicable Section 515 and 615 MPS (4900.1 and 4910.1) - Part C ANSI A119.1 - Hazards not significantly greater than conventional residential installation	- Personnel exposure to high temperatures - Personnel exposure to high pressures - Equipment damage - Contamination of potable water - Primary 115 Volt Shock - Shorts from primary 115V to 24V control circuits - Damage to collector by over temperature - Control failures	- Used commercially available DHW tanks, pumps and heat exchanger of proven design - Automatic 210°F temperature and 150 PSI pressure relief valve - Stainless steel potable rated DHW pump - Fail Safe DHW temperature control on both water tanks - Insulated heat exchanger and connecting pipes - Non potable fluid not used - Safety shield used over primary terminal and shrink sleeving used on 115V wire terminals within service area. - Primary and control voltages transformer isolated with wiring physically separated - Collector temperature protect mode for summer operation - Autonomous temperature limits and interlocks within control circuits
J-6 Control	Fail Safe control		

HAZARD DATA SUMMARY

Areas of Consideration	Safety Requirement	Hazard/Undesired Event	Means of Compliance
J-7 Auxiliary Heat	• Section 516 and 616 MPS (4900.1 and 4910.1) • Part C ANSI A119.1 • UL acceptance	• Primary 115 Volt Shock	• Primary 115 Volt circuit terminations enclosed
		• Toxic or Flammable materials • Rotating Equipment entanglement • Electrical Shock • Fire hazard if air flow interrupted • Excessive surface temperatures	• Over temperature protected motor • UL approved wire nuts • Use commercial components of proven design • Independent review of material hazards • UL acceptance of the completed air handler and controller assembly • Fan, motor and belt totally enclosed • Use conventional equipment of proven design and installation • Primary power terminations enclosed • Control interlocks between fan and heat strips • Positive action air flow velocity switch interlock • Heater installed in insulated duct